

**SURVEY & REMONUMENTATION**

MAR 21 1997

COMMISSION

**REMONUMENTATION  
SECTIONS 16 & 17, OLIVE TOWNSHIP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Clinton	Located In	Corner Code #
1. Public Land Survey	T 6N R 2W	E 6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED

Oct 11 8 53 AM '96

CLINTON COUNTY, MICH.  
*Arden S. Pierson*

LIBER 4, PAGE 168

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Arden S. Pierson P.S., in a field survey on August 13, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ◆ Original survey by Hervey Parke, DS, 1826. Set 1/4 Section Post, witnessed by: Tamarack 7" - S50°E - 2 links; Tamarack 7" - N19-1/2°E - 11 links.
- ◆ LCRC by Clyde Stephens, PS, #3829, dated May 26, 1972, Liber 1, pages 419- 420. A 3/4" iron pipe was set in the centerline of the section line road (Loomis Road) and on a projection of an old fence East of the corner. Witnessed by:  
Survey tag in the E. Side of a Utility Pole - N77°03'W - 312.20'  
Survey tag in the top of a fence post - N75°52'E - 29.20'  
Survey tag in the top of a fence post - S89°46'E - 28.38'  
The bearing of the section line north of the corner is North.

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod. (Also found buried, boiler tube culvert.) Accepted as a careful and faithful reestablishment of the position of the original corner.


\*Set Standard Clinton County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 Corner Common to Sections 16 & 17

- \*Set Standard Clinton County Monument  
Nail & tag #13039 in W. side Telephone Pole - N11°E - 258.20'  
Nail & tag #13039 in N. side Pole Anchor Post - S85°W - 30.73'  
Nail & tag #13039 in SW side Power Pole - S30°E - 52.48'  
Nail & tag #13039 in NE Corner 6"x6" Gate Post - S50°E - 32.92'

\*Standard Clinton County Monument is a 2 1/2" dia. Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by *Arden S. Pierson*  
Surveyor's Michigan License No. 13039

Date August 15, 1996

APPROVED BY  
CLINTON COUNTY P.E.R. GROUP  
DATED 8/21/96  
872

- ◆ Certificate of Survey by James Stephens, PS, #16053, dated May 25, 1973, Liber 1, page 328.
- ◆ Certificate of Survey by LaVerne Hendryx, PS, #3276, dated June 20, 1973, Liber 1, page 342.
- ◆ Certificate of Survey by James Stephens, PS, #16053, dated July 17, 1973, Liber 1, page 348.
- ◆ Certificate of Surveys by Ronnie Lester, PS, #18998, dated May 1989, Liber 3, pages 371-374. 5/8" rerod, witnessed by:
  - Stephens nail & tag in top post - 97° az. - 28.4'
  - Stephens nail and tag in top post - 84° az. - 29.4'
  - Set nail and tag in N. Side fence post - 265° az. - 30.5'
  - Set nail and tag in West side Utility pole - 150° az. - 52.3'
  - Set nail and tag in West side North gate post - 130° az. - 32.8'