

**SURVEY &  
REMONUMENTATION**

**FEB 02 1998**

**REMONUMENTATION**

**SECTION**

**SECTION 32, OLIVE TOWNSHIP**

**LAND CORNER RECORDATION CERTIFICATE**

Fileing Requirement of Act 74, Mich. P.A. 1970

**LIDER 004 PAGE 233**

**RECORDED**

**Oct 17 9 20 AM '97**

REGISTERED  
CLINTON COUNTY, MICH.  
*Arden Pierson*

Register of Deeds Stamp & File Number

For corners in <u>Clinton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>2W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Arden S. Pierson, PS, in a field survey on July 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- ◆Original survey by Hervey Parke, DS, 1826. Set post corner to Section 32 & 33, witnessed by: W. Oak 15" - N72°E - 39 links; Maple 7" - N79°W - 29 links.
- ◆Survey by Charles Hollister, County Surveyor, January 28, 1890. Found a stone set to mark the corner of sections 32 and 33 on range line and one witness tree W. Oak 30" - S5°E - 67 links.

(over)

APPROVED BY  
CLINTON COUNTY P.E.R. GROUP  
DATED 8/20/97  
*J.F.P.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1/2" rod over pointed stone down 30" below asphalt. Accepted 1/2" rod as a careful and faithful perpetuation of the position of the original corner.

Left stone in place and placed Standard Clinton County Monument over stone in monument box.

(Closing Corner for T5N, R2W, is 29.61' West)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Southeast Corner, Section 32
- \*Standard Clinton County Monument and monument box
- SE Corner Concrete Fence Post - N02°E - 30.96'
- Nail & tag #13039 in NW side Power Pole - N53°E - 46.52'
- Nail & tag #13039 in East side 21" Hickory - S25°W - 52.76'
- Nail & tag #13039 in North side 14" Oak - S68°E - 109.91'
- To D-13, T6N, R2W, N89°39'03"W. 2639.62'
- To E-13, T6N, R2W, S89°49'00"E. 2638.26' From solar observations.
- \*Standard Clinton County Monument is a 2 1/2" diameter Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by *Arden S. Pierson* Date July 29, 1997  
Surveyor's Michigan License No. 13039

◆Clinton County Surveyor Field Notes -- Witnessed by W. Oak 30" - S5°E -  
67 links.

◆LCRC by Richard W. Steadman, PS, #11370, dated March 8, 1976, Liber 2,  
Page 120. Dug hole in Cutler Road opposite fence line North and just below  
the surface, found a pointed stone. Excavation had to be made very  
carefully because of buried telephone cable passing near the stone and 6"  
below the surface. Witnessed by:

Telephone pole - S51°E - 46.41'  
8" Ash in clump - South - 45.25'  
12" Hickory - S25°W - 52.55'

LIBER 001, PAGE 234

◆Certificate of survey by Fred N. White, PS, #12034, dated November 22,  
1978, Liber 2, Page 134. ?