

SURVEY & REMONUMENTATION

FEB 02 1998

SECTION

**REMONUMENTATION
SECTION 33, OLIVE TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 004 PAGE 235

RECORDED

Oct 17 9 20 AM '97

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Arden S. Pierson

Register of Deeds Stamp & File Number

For corners in <u>Clinton</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>2W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Arden S. Pierson, PS, in a field survey on July 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ◆ Original survey by Hervey Parke, DS, 1826. Set ¼ Section post, witnessed by: Red Oak 21" - N40°E - 61 links; W. Oak 15" - N78°W - 14 links.
- ◆ Survey by Chas. E. Hollister, County Surveyor, 1890. Set stone for quarter post by division, witnessed by: Hickory 7" - N39¼°E - 36¼ links; Hickory 9" - N49°W - 39¼ links.
- ◆ Clinton County Surveyor Witness Notes -- Stone, witnessed by: Hickory 7" - N39¼°E - 36¼ links; Hickory 9" - N49°W - 39¼ links. Stone set North 50 links.

(OVER)

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/20/97
J-73

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron and cap over ½" iron and cap. Accepted ½" iron and cap over ½" iron and cap as a careful and faithful re-establishment of the position of the original corner:

Replaced with Standard Clinton County Monument.

Closing corner is west 22.39'.

C. Description of monument for corner and accessories established to perpetuate locating the position

South ¼ Corner, Section 33

*Standard Clinton County Monument and monument box
Nail & tag #13039 in SE side Power Pole - N54°E - 59.70'
Nail & tag #13039 in NW side 13" Hickory - S32°W - 38.58'
Nail & tag #13039 in SE side 24" Oak - S72°W - 91.41'
Nail & tag #13039 in SW side Power Pole - N60°W - 82.90'
To E-13, T6N, R2W, N89°49'00"W. 2638.26'. To G-13 T6N, R2W, S89°35'35"E 2637.78'. From solar observations.

*Standard Clinton County Monument is a 2½" diameter Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by *Arden S. Pierson*

Date July 29, 1997

Surveyor's Michigan License No. 13039

◆LCRC by Ron Helsel, PS, #18994, dated November 7, 1972, Liber 1, Page 597.
Found North $\frac{1}{4}$ Corner Section 4, DeWitt Township. Set Corner East 22.57' of said
North $\frac{1}{4}$ Corner (GLO 22.77') by single proportionate measurement along township
line. Witnessed by:

West - 22.57' - $\frac{3}{4}$ " Pinch Pipe - (North $\frac{1}{4}$ Corner Section 4, DeWitt Twp.)
S25°E - 25.16' - Nail & tag 12" Black Walnut
N66°W - 88.68' - Nail & tag 10" Ash
S60°W - 67.44' - Nail & tag 15" Oak

LIDER 004 PAGE 236

◆Certificate of Survey by Ron Helsel, PS, #18994, dated November 22, 1972, Liber 1, Page 246.

◆Certificate of Survey by Arden S. Pierson, PS, #13039, dated August 25, 1977, Liber 1, Page 962.

◆Certificate of Survey by Fred N. White, PS, #12034, dated November 22, 1978, Liber 2, Page 134.

◆Certificate of Survey by Douglas K. Richardson, PS, #31603, dated February 18, 1993, Liber 4, Page 693.