

SURVEY & REMONUMENTATION

FEB 02 1998

SECTION

REMONUMENTATION SECTION 34, OLIVE TOWNSHIP LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 204

RECORDED

Oct 17 9 17 AM '97

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

David W. Kelly

For corners in

Clinton _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>2W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	4	5	6	7	8	9	10	11	12	13	14	15	16
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Mark L. VanRaemdonck, in a filed survey on August 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original Lucius Lyons 1826
Mon: Wood Post
Access: Elm 6 N63°E 35
DO 7 N46°W 25
- Hollister Field Book 2, P. 29-31
Shows between corners H-13 and G-13 as 39.94 chains (2636.04). He states that "both witnesses given in U. S. Survey Note are still standing."
- Fred N. White, L. C. R. C. I. 1, p. 327 4/17/72
Mon: Set Nail & Tag by proportional measurements
Access: 5" Ash North 33.11
5" Ash M35°W 37.04
5" Pine Anchor Post 27.31

(continued on reversed side of this sheet)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Rerod in Mon. Box as referenced in No. 3, 4, 5, 6, and 7 above. I accepted this location as the careful and faithful re-establishment of the original corner position.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Removed rerod and replaced it with a standard Clinton County Remonumentation Monument. The monument is witnessed by the following accessories:
 N89°41'13"W 9.84' STD Clinton County Mon at H-1, T5N-R2W
 S89°41'13"E 2634.34' STD Clinton County Mon at I-13, T6N-R2W
 S25W 34.17' Nail & Tag #24622 in E. face 10' Poplar
 S05W 26.79' Nail & Tag #15039 in W. face 12" Poplar
 N30W 45.01' Nail & Tag #25832 in E. face 18" Poplar

Signed by Mark L. VanRaemdonck

Date SEPT 8, 1997

Surveyor's Michigan License No. 24622



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
REVISED MAY 14, 1975
REVISED JAN. 1993

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 9/13/97

J. J. J.

A. Description of original monument and accessories and/or subsequent restoration:

(continued from front)

4. Ronnie Lester, Cert. Survey L. 2, P. 940. 9/13/86

Mon: Bar in Mon. Box

Access: Centerline of Mon. Box West 9.8'

Nail & tag in NE side P. P. SE 82.2'

Nail & tag in West side 18" Ash North 30.6'

Nail & tag in West side 10" Poplar South 26.7'

LIBER 004 PAGE 205

5. Larry Bryan, Cert. Survey L. 3, P. 225 7/14/88

Mon: 1/2" bar in Mon. Box

Access: Nail & tag in NE side P. P. SE 82.2'

Nail & tag in West side 18" Ash North 30.6'

Nail & tag in West side 10" Poplar South 26.7'

6. Richard Steadman, Cert. Survey L. 4, p. 349 9/24/91

Mon: 3/4" iron pipe in Mon. Box

Access: 5" Ash North 33.11'

5" Ash N35°W 37.04'

1/2" iron pipe South 33.00'

7. Richard Steadman, Cert. Survey L. 4, P. 531 9/24/91

Mon: 3/4" iron pipe in Mon. Box

Access: 5" Ash North 33.11'

5" Ash N35°W 37.04'

1/2" iron pipe South 33.00'