

**SURVEY &
REMONUMENTATION**

**REMONUMENTATION
SECTION 2, OLIVE TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

JAN 17 1996

COMMISSION

RECORDED

For corners in

Clinton
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>6N</u>	R	<u>2W</u>	<u>I-1</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

SEP 27 9 14 AM '95

REGISTER DEEDS
CLINTON COUNTY, MICH.
Arden S. Pierson

LIBER 4, PAGE 71

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

Arden S. Pierson P.S., in a field survey on August 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original survey by Hervey Parke in 1827.
76.85' chains intersect town line 43 Links west
B. Oak 9" - S75½°W - 35 Links, 8" B. Oak - S59¼°E 29 Links
- County Survey Notes by Charles Hollister, December 1880,
Sugar 2" - N65¼°E - 95 Links, Hickory 2" - S80¼°E 2.29 Links.
- LCRC Liber 2, Page 328 by Russell Roon PS, 9/17/80 - Found stake & stone, placed monument box over, 26" maple - N61°E - 62.87'; 13" Maple - S74°E - 81.60'; 3" Maple - N64°E - 73.25'; Face Hickory - S80°E 150.00'; East 28.38' to Bingham corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

7/07/93 - Recovered described monument - chiseled "+" in pointed stone with monument box.
1994 - Set Standard Clinton County Monument in monument box after road reconstruction.
1995 - Verified corner position.
Accepted stone as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NW Corner, Section 2, Olive Township

*Standard Clinton County Monument
Nail & tag #13039 in W. side 6" Red Cedar - S15°E - 103.99'
Nail & tag #13039 in E. side 42" Willow - S35°E - 107.99'
Nail & tag #13039 in E. side 16" Cherry - S02°W - 103.14'
Nail & tag #13039 in NE side 28" Walnut - N02°W - 115.01'
(Found ½" iron - NE - 17.95', Found 1½" Pipe - NW - 8.92')
Standard Corner - East - 28.38'
*Standard Clinton County Monument is a 2½" dia. steel base long with a stamped brass cap and a breakaway magnet.

Signed by

Arden S. Pierson

Date

September 9, 1995

Surveyor's Michigan License No. 13039

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JUL 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/30/95
S 79

