

SURVEY & MONUMENTATION
REMONUMENTATION
SECTION 2, OLIVE TOWNSHIP

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in Clinton (County) **COMMISSION** Located In:

Corner Code #

1. Public Land Survey	T	<u>6N</u>	R	<u>2W</u>	<u>J-1</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

SEP 27 9 14 AM '95

REGISTERED CLINTON COUNTY CLERK

Barbara M. ...

LIBER 4, PAGE 73

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13	12	11	10	9	8	7
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	30	29	28	27	26	25	24	23	22	21	20
13												

Arden S. Pierson P.S. in a field survey on August 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Original survey by Hervey Parke in 1827. (This corner was not set in original survey.)
2. County Survey Notes by Charles Hollister, December, 1880; Drove iron bolt on N. line, Section 2;
3. LCRC Liber 2, Page 328 by Russell Roon PS, dated 9/17/80 - No point found. Set 3/4" pipe from Oak tree and 5.94' south of line as called for in 1880 survey. 43" White Oak - N75°W - 73.06'; 18" Red Oak - N44°E - 27.17'; Corner Fence Post - S08°W - 24.75'; East 14.29' to Bingham corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11/16/93 - Found 3/4" pipe, as recorded, verified witnesses and rewitnessed to preserve position.

1994 - Reset corner after reconstruction of Centerline Road, placed Standard Clinton County Monument and rewitnessed.

1995 - Verified corner witnesses.

The corner position is accepted as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- *Standard Clinton County Monument
 Top Center 2" Steel Anchor Post - N55°W - 227.68'
 Nail & tag #13039 in E. side Power Pole - S13°W - 165.30'
 Nail & tag #13039 in E. side 12" Elm - S04°W - 49.95'
 Nail & tag #13039 in E. side 4" Oak - S05°E - 42.62'
 Bingham Township Corner - East - 14.28'

*Standard Clinton County Monument is a 2 1/2" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base

Signed by Arden S. Pierson

Date September 9, 1995

Surveyor's Michigan License No. 13039

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971

APPROVED BY
 CLINTON COUNTY PEER GROUP
 DATED 8/30/95
AJP

