

JAN 17 1996

COMMISSION

REMONUMENTATION SECTION 2, OLIVE TOWNSHIP LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Clinton (County)

Located In:

Corner Code #

RECORDED

SEP 27 9 14 AM '95

REGISTERED BY CLINTON COUNTY

Arden S. Pierson

LIBER 4, PAGE 74

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 6N R 2W J-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A black dot is located at the intersection of column J and row 3.

Arden S. Pierson P.S. in a field survey on August 1, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original survey by Hervey Parke in 1827. Set 1/4 Sec. Post on True Line, W. Oak 20" - S79°E 23 Links; W. Oak 24" - N84°W - 29 Links.
2. County Survey Notes by Charles Hollister, December 1880 - Post - 3" Yellow Oak - S88°E - 65 1/2 Links, 8" B. Oak - N17 1/2°E - 156 1/4 Links.
3. LCRC Liber 2, Page 331 - by Russell Roon, 9-17-80 - Found hole from which post had been removed; 16" Hickory - N05°E - 3.44'; 16" Hickory - N25°W - 18.32'; 14" Beech - N70°W - 37.58'; 17 Maple - N80°E - 5.05'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Replaced corner monument from MDOT coordinate geometry - traversed perimeter of Section 2, tie to SE corner of Section 2 as shown on the construction plans is defective.

The corner position is accepted as a careful and faithful perpetuation of the original corner.

Set Standard Clinton County Monument and carsonite marker.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 Corner, Section 2

*Standard Clinton County Monument

Nail & tag #13039 in W. side Power Pole - N12°W - 158.46'

West end culvert - N87°E - 98.51'

Nail & tag #13039 in N. side 3" Ash - S65°E - 133.18'

*Standard Clinton County Monument is a 2 1/2" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base.

Signed by

Arden S. Pierson

Date



Surveyor's Michigan License No.

13039

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

APPROVED BY CLINTON COUNTY PEER GROUP DATED 8/30/95

Signature