

**SURVEY &
REMONUMENTATION**

FEB 02 1998

SECTION

**REMONUMENTATION
OLIVE TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich.P.A. 1970**

LIDER 004 PAGE 206

RECORDED

OCT 17 9 17 AM '97

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

David Wooley

For corners in

Clinton (County)	Located in:	Corner Code #
1. Public Land Survey	T_6N__ R_2W__ T____ R____ T____ R____ T____ R____	_K-13_____
2. Property Controlling In Section	S____ T____ R____ S____ T____ R____	_____
3. Miscellaneous Property in Sec.	S____ T____ R____ S____ T____ R____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark L. VanRaemdonck, in a filed survey on August 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original Lucius Lyons 1826
Mon: Wood Post
Access: W. Oak 12 N47°E 71
DO 17 N22°W 66
- County Surveyor Hollister Field Book 2, P. 157 August 19-1899
Mon: Stone
Access: Apple 5 S35 3/4°E 94
B. Oak 38 N28 1/2° W 161
- Glen Fauser, Cert. Survey L.1, P. 860 2/7/77
Mon: Found Sq stone with small stones around - set rerod over stone
Access: Steel Post E. 13.6 centerline
P. Pole East 34.45 feet
Monument East 33.88
SW corner house foundation NE 99.64
12" Oak SW 50.62
- Edwin Morse L.C.R.C. L.2, P. 294 6/13/80
Mon: Found stone raised with Bar & Cap #18657
Access: N50°E 166.23' NW Cor. house foundation
S85°E 33.90' Conc. property Monument
South 138.26' M.D.S.H. Ref. tag in 26" Oak
S55°W 50.56' M.D.S.H. Ref. tag in 14" Oak

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" Rerod and Stone in Mon. Box as referenced in No. 3 and 4 above. Accepted this position as the careful and faithful perpetuation of the original corner location.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Removed 1/2" Rerod and Stone and replaced them with a standard Clinton County Remonumentation Monument. The Monument is witnessed by the following accessories:
 N75W 42.41' Set Nail & Tag #24622 in N. face 12" Oak
 S45W 50.22' Set Nail & Tag #24622 in N. face 24" Oak
 East 34.44' M.D.O.T. reference tag in South face util pole
 North 148.3' Centerline asphalt pavement Round Lake Road
 N89°41'17"W 15.29' STD Clinton County Mon at K-1, T5N-R2W
 S89°41'24"E 2640.02' STD Clinton County Mon at L-13, T6N-R2W

Signed by *Mark L. VanRaemdonck*

Date SEPT. 8, 1997

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

APPROVED BY
 CLINTON COUNTY PEER GROUP
 DATED 8/13/97