

SURVEY & REMONUMENTATION

FEB 02 1998

**REMONUMENTATION
OLIVE TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 207

SECTION

For corners in

Clinton (County)	Located in:	Corner Code #
1. Public Land Survey	T_6N__R_2W__	L-13
	T_____R_____	_____
	T_____R_____	_____
	T_____R_____	_____
2. Property Controlling In Section	S_____T_____R_____	_____
	S_____T_____R_____	_____
3. Miscellaneous Property in Sec.	S_____T_____R_____	_____
	S_____T_____R_____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

Oct 17 9 18 AM '97

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

David W. Wadley

I, Mark L. VanRaemdonck, in a filed survey on August 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original Lucius Lyons 1826
Monument Wood Post
Accessories:
A. Cherry 8 N75°E 17
B. Oak 6 N28°W 29
- Marvin Fouty Certified Survey
Monument 1/2" Bar & Cap over square stone
Accessories:
A. P. K. in 18" Oak S25°E 28.27
B. P. K. in 14" Oak S70°E 21.37
C. P. K. in 9" Oak N5°E 26.35'
- Marvin Fouty Certified Survey L. 2, P. 572 4/4/83
Monument 1/2" Bar & Cap over square stone
Accessories:
A. P. K. in 18" Oak S25°E 28.27
B. P. K. in 14" Oak S70°E 21.37
C. P. K. in 9" Oak N5°E 26.35'
- Marvin Fouty, Certified Survey L. 2, P. 674 11/17/83
Monument 1/2" Bar & Cap over square stone
Accessories:
A. P. K. in 18" Oak S25°E 28.27
B. P. K. in 14" Oak S70°E 21.37
C. P. K. in 9" Oak N5°E 26.35'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" rod with cap #18657 and pointed stone (square) as referenced in No. 2 above. Accepted this position as the original corner location based on the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Removed 1/2" rod & cap and stone, replaced them with a STD, Clinton County Monumentation Monument. The monument is witnessed by the following accessories:

- S20E 28.88 Set Nail & Tag #24622 in W. face 24" Oak
- S50E 22.18 Set Nail & Tag #24622 in SW face 18" Oak
- N10E 13.93 Set Nail & Tag #24622 in W. face 10" Cherry Tree
- N89°41'24"W 7.60' STD Clinton County Mon at L-1, T5N-R2W
- S89°43'28"E 2638.15' STD Clinton County Mon at M-13, T6N-R2W

NOTE: Monument is 660 feet more or less South of Round Lake Road.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date SEPT 8, 1997

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/19/97
J. J. J.