

JAN 17 1996

REMONUMENTATION SECTION 13, OLIVE TOWNSHIP

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in Clinton (County)

Located In:

Corner Code #

Table with 3 columns: Description, Located In (T, R, S), and Corner Code # (M-6). Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

Nov 9 9 03 AM '95

REGISTER OF DEEDS CLINTON COUNTY, MICH.

Carole Woolley

LIBER 4, PAGE 103

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

Arden S. Pierson P.S. in a field survey on September 15, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lucius Lyon, DS, in 1826. Set Half Mile Post, witnesses:

Hickory 7" - S6°W - 20 links (13.20')
W. Oak 15" - N69-1/2°W - 52 links (34.32')

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod in monument box September 15, 1995. Removed 5/8" iron and monument box, excavated 18" x 18" area, 3' deep found 5/8" rod - 25" below road surface. Accepted 5/8" rod as a careful and faithful perpetuation of the original corner.

Set Standard Clinton County Monument and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position:

East 1/4 Corner, Section 13

\*Standard Clinton County Monument in monument box
NW Corner House #7511 - S61°E - 94.75'
SE Corner House #7486 - N35°W - 98.60'
SW Corner House #7511 - S43°E - 117.45'
R.R. Spike - North - 19.76'

\*Standard Clinton County Monument is a 2 1/2" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base.



Signed by Arden S. Pierson

Date October 16, 1995

Surveyor's Michigan License No. 13039

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

APPROVED BY CLINTON COUNTY PEER GROUP DATED 10/18/95 S. 7-9

9/15/95

**LCRC Liber 1, Page 811, dated August 20, 1972, by Hathaway Hanes #5260.**

Found 3/4" pipe  
NW Corner House 75.1' - S80°E - 90.7'  
24" Oak - S45°W - 40.5' - P.K.  
14" Bitternut - S70°W - 48.85' - P.K.

**Certified Boundary Survey by Hathaway Hanes #5260 dated August 8, 1972, Liber 1, Page 157.**

3/4" pipe found.  
No witnesses given.

**Certified Boundary Survey by Hathaway Hanes #5260 dated May 23, 1973, Liber 1, Page 319.**

Corner unknown  
30" W. Oak - N75°W - 32.17'  
9" Aspen - N80°E - 23.50'  
12" Twin Ash - S10°E - 27.65'

**Survey by Arden Pierson dated October 19, 1993.**

Found 5/8" rod in monument box.  
NW Corner House #7511 - S61°E - 94.75'  
SE Corner House #7486 - N35°W - 98.60'  
SW Corner House #7511 - S43°E - 117.45'  
R.R. Spike - North - 19.76'

**Certified Boundary Survey by Arden Pierson #13039 dated February 21, 1994, Liber 4, Pages 993-994.**

Found 5/8" rod in monument box.  
NW Corner House #7511 - S61°W - 94.75'  
SE Corner House #7486 - N35°W - 98.60'  
SW Corner house #7511 - S43°E - 117.45'  
Railroad Spike - North - 19.76'

**LCRC dated February 23, 1994, by Arden Pierson #13039.**

Found 5/8" rod in monument box.  
NW Corner House #7511 - S62°W - 94.75'  
SE Corner House #7486 - N35°W - 98.60'  
SW Corner House #7511 - S43°E - 117.15'  
Railroad Spike - North - 19.76'