

SURVEY & REMONUMENTATION

FEB 02 1998

**REMONUMENTATION
SECTIONS 33 & 34, RILEY TOWNSHIP**

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIDER 0014 PAGE 237

For corners in

| CLINTON (County) | Located In: | Corner Code # |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T <u>6N</u> R <u>3W</u> | <u>G - 13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED

OCT 17 9 20 AM '97

REGISTERED AS DEEDS
CLERK OF COURTS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Roger P. Mahoney, in a field survey on July 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13 - Southeast Corner Section 33 and Southwest Corner Section 34, T.6N.-R.3W.

Post set by Deputy Surveyor L. Lyons in 1826;
Beech 20", N.61°E., 45 links
Elm 18", N.44°W., 38 links

(Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 - Southeast Corner Section 33 and Southwest Corner Section 34, T.6N.-R.3W.

Found Standard Clinton County Monument being 2 1/2" diameter steel tube, 30" long with a stamped brass cap, set by P.S.# 34976. Also found various witnesses from certificate of surveys and L.C.R.C. recorded in L. 1, P. 339.

Accepted the found monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 - Southeast Corner Section 33 and Southwest Corner Section 34, T.6N.-R.3W.

Standard Clinton County Monument being 2 1/2" diameter steel tube, 30" long with a stamped brass cap, restamped # 41105

N.45°W., 34.32'--N&T, # 12034, SW, face 20" Twin Ash
S.45°W., 55.15'--N&T, # 12034, NW, face utility pole
N.75°W., 118.86'--N&T, # 12034, S. face 24" Maple
N.65°E., 72.23'--N&T #, 12034, SE face utility pole
East 28.33'--Remonumentation corner, G - 1, T.5N.- R.3W., Watertown Township



Signed by Roger P. Mahoney
Surveyor's Michigan License No. 41105

Date August 20, 1997

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/20/97
S 78

Post on Town Line by County Surveyor C. E. Hollister, 1876, Field Book 7, P. 60;
Willow 12", S. 1 1/2° W., 135 links
B. Walnut 8", N. 57° W., 157 1/2 links

County Surveyor C. E. Hollister, Nov. 20, 1879, Found stone set and one witness to _____ Watertown corner, 43 links East of this corner;
Willow 12", S. 1 1/2° W., 135 links
B. Walnut 8", N. 57 1/2° W., 157 1/2 links

Clinton County Road Commission Alignment Notes, 1920+/-, Vol. 3, P. 16, 1" iron pipe, 6" down;
10" Walnut, S. 17°-20' W., 31.2'
1" iron pipe, N. 78°-30' E., 64.1'
1" iron pipe, S. 58°-0' E., 79.3'

L.C.R.C. by F. White, # 12034, May 1972, Recd. L.1, P. 339, found R.R. spike;
N.55°10'W., 35.05'--Anchor Pole
S.43°40'W., 55.33'--Power Pole
N.58°30'E., 72.36'--Anchor Pole

L.C.R.C. by F. White, # 12034, July 1972, Recd. L. 1, P. 389, found R.R. spike;
N.55°10'W., 35.05'--Anchor Pole
S.43°40'W., 55.33'--Power Pole
N.58°30'E., 72.36'--Anchor Pole

Certificate of Survey by F. White, # 12034, July 1972, Recd. L.1, P. 153, R.R. spike in centerline of Cutler Road and Francis Road extended from north;
N.55°10'W., 35.05'--Anchor Pole
S.43°40'W., 55.33'--Power Pole
N.58°30'E., 72.36'--Anchor Pole

Certificate of Survey by R. Helsel # 1899- Oct. 1974, Recd. L. 1, P. 523, refers to corner Recd. L.1, P. 389

Certificate of Survey by J. Stephens, # 1603, May 1979, Recd. L. 2, P. 170, R.R. spike with witnesses of:
N.55°10'W., 35.05'--Tag in Anchor Pole
S.43°40'W., 55.33'--Tag in Power Pole
N.58°30'E., 72.36'--Tag in Anchor Pole
Recorded in L.1, P. 389

Certificate of Survey by M. VanRaemdonck, # 2462, April 1983, Recd. L.2, P.551, found R.R. spike;
S.45°W., 55.30'--C.P. Co. Tag in Utility Pole
N.10°W., 30.20'--N. End 24" C.M.P.
N.75°E., 72.40'--C.P. Co.

Certificate of Survey by M. VanRaemdonck, June 1991, Recd. L. 4, P. 287, found R.R. spike;
S.45°W., (no distance given), C.P. Co, Tag in N. Face
S.50°W., 55.30'--Utility Pole
N.60°W., 34.25'--Top center telephone cable box
S.65°W., 81.36'--Center N. Face 6" White Birch
East, 17.90'--Phys. centerline asphalt surface

Certificate of Survey by R. Mahoney, # 41105, Feb. 1997, found Clinton County Remon Tablet;
N.45°W., 34.32'--N&T, # 12034, SW Face 20" Twin Ash
S.45°W., 55.15'--N&T, # 12034, NW Face Utility Pole
N.75°W., 118.94'--N&T, # 12034, S. Face 24" Maple
N.65°E., 72.30'--N&T, # 12034, SE face Utility Pole