

SURVEY &  
REMONUMENTATION ON **REMONUMENTATION**  
**SECTION 16, WESTPHALIA TOWNSHIP**

**JAN 17 1996**      **LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**  
Clinton  
(County)

Located In:

Corner Code #

RECORDED

- |                                      |   |           |   |           |            |
|--------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey                | T | <u>6N</u> | R | <u>4W</u> | <u>E-6</u> |
|                                      | T | _____     | R | _____     | _____      |
|                                      | T | _____     | R | _____     | _____      |
|                                      | T | _____     | R | _____     | _____      |
| 2. Property Controlling In Section   | S | _____     | T | _____     | R          |
|                                      | S | _____     | T | _____     | R          |
| 3. Miscellaneous Property In Section | S | _____     | T | _____     | R          |
|                                      | S | _____     | T | _____     | R          |

Dec 19 2 51 PM '95

RECORDED BY  
CLINTON COUNTY DEEDS CLERK  
*Carol J. [unclear]*

**LIBER 4, PAGE 122**

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	6	5	4	3	2					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**Arden S. Pierson P.S.**, in a field survey on October 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original survey performed by Lucius Lyon DS - 1927.  
40.00 chains - Set 1/2 Mile Post.  
15" Beech - S56°W - 21 links  
9" Beech - S59°E - 8 links

(OVER)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1/4 Corner Common to Sections 16 & 17, T6N, R4W. Found 5/8" rod in monument box. Removed 5/8" rod and monument box, found 5/8" rod 24" below road surface, found stone 2.8' below road surface. Set Standard Clinton County Monument and Monument Box. Accepted 5/8" rod in monument box as a careful and faithful perpetuation of the position of the original corner.

APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 11/8/95  
*[Signature]*



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**West 1/4 Corner, Section 16**

- \*Standard Clinton County Monument in monument box
- Nail & tag #13039 in SW Side 10" Red Cedar - S37°E - 54.89'
- NW Corner House Foundation - S46°E - 125.56'
- Nail & tag #13039 in North Side 10" Red Cedar - S75°E - 38.06'
- SW Corner Pole Barn - N65°E - 122.14'

\*Standard Clinton County Monument is a 2 1/2" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base.

Signed by *[Signature]*

Date November 4, 1995

Surveyor's Michigan License No. 13039

**County Surveyor Notes for Section 17, Westphalia Township made by Charles Eddy - Surveyor (1891 - 1902).**

E  $\frac{1}{4}$  Corner of Section 17 is common to West  $\frac{1}{4}$  of Section 16 (E-6) :

Found Stone with stake and crockery around.

9" Elm - N86°W - 41 links  
10" Elm - N85°E - 56 links

**Clinton County Road Commission Alignment Field Notes related to U.S. Public Land Survey Corners (1920+/-).**

PA 74 of 1970

E-6: 52 + 63.4 (station) 1/4 Corner Common to Sections 16 & 17. Stone not dug up. Sta. 0 Ass'mt. Dist.  
Road #7 used as point of ending.

3 - 1" gal. iron pipes

**Witnesses:**

N46°40'W - 40'  
N45°15'E - 45'  
S45°20'E - 40'