

CLINTON

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>34</u> T. <u>7</u> <u>N.</u> , R. <u>1</u> <u>W.</u>		<u>H-13</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. _____, W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. _____, W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

(7) H-13

I, Donald L. Bissell do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 8 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Half mile post on S. boundary Section 34, T7N, R1W  
W. Oak 30", N27<sup>0</sup>E, 28 lks.  
Cherry 14", N24<sup>0</sup>W, 16 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Found pointed stone  
no old witnesses

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Pointed stone  
placed metal and crockery around stone  
N70<sup>0</sup>W, 58.2', 16" Hickory, spike  
N27<sup>0</sup>W, 27.7', Triple 4", 5" & 6" Cherry, spike  
North, 3', ← old road