

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	34 T. 7 N. R. 1 W.	H-12
2. PROPERTY CONTROLLING IN SECTION	T. S. R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, **Donald L. Bissell** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram) were, in a field survey on _____ 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on **October 8** _____ 19 **73**, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Not set in original survey.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found pointed stone (1890 survey)
old witnesses tree
S 66½° W, 13.20', 26" W. Oak (formerly 4" W. Oak)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

Pointed stone 0.2' below ground
S 66½° W, 13.20', 26" W. Oak, spike (old bearing tree)
N 12° W, 24.91', 13" R. Oak, spike
S 83° E, 34.25', 21" Hickory, spike