

**REMONUMENTATION**  
**SECTION 14, BINGHAM TOWNSHIP**  
**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

Nov 9 9 02 AM '95

REGISTER OF DEEDS  
 CLINTON COUNTY, MICH.  
*Arden S. Pierson*

For corners in  
Clinton  
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>7NR</u> <u>2W</u>	<u>J-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 4, PAGE 89

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5										●		
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

Arden S. Pierson P.S. in a field survey on August 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*Original survey of Bingham Township by C.W. Christmas in 1831.*  
*County surveyor notes by Charles Eddy, dated May 1, 1902.*  
*N ¼ Post Section 14 - Found stake for corner, set stone over stake from which a 4" walnut N52½°E 80 links*

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*Found ¼" rod in monument box.*  
*Set witness irons for corner replacement after reconstruction of Highway M-21 (5-05-95). The ¼" rod is accepted as a careful and faithful re-establishment of the position of the original corner.*  
*Set Standard Clinton County Monument and monument box on October 13, 1995.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**North ¼ Corner, Section 14**  
 \*Standard Clinton County Monument in monument box.  
 Nail & Tag #13039 in W. Side Power Pole - N06°E - 58.84'  
 SW corner brick garage - N20°E - 121.69'  
 SE corner brick house - N44°E - 157.49'  
 Nail & Tag #13039 in SW Side Telephone Pole - N70°W - 229.96'  
 \*Standard Clinton County Monument is a 2½" dia. steel tube 30" long with a stamped brass cap and a breakaway magnetic base

Signed by *Arden S. Pierson* Date \_\_\_\_\_  
 Surveyor's Michigan License No. 13039

APPROVED BY  
 CLINTON COUNTY PEER GROUP  
 DATED 8/30/95  
A 78

October 14, 1995

STATE OF MICHIGAN  
 ARDEN S. PIERSON  
 PROFESSIONAL SURVEYOR  
 No. 13039

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1988 REVISED MAY 14, 1990 REVISED JAN. 19, 1995

LIBER 4, PAGE 90

From LCRC Liber 2, Page 334  
By Russell L. Roon, PS 13593

(North  $\frac{1}{4}$  Corner, Section 14, T7N, R2W)  
Corner monument destroyed by building Highway M-21.  
Set copperweld rod and aluminum cap in monument box.  
Set corner from "Blue Water Subdivision."

North 60.00' - iron rod in concrete monument  
N50°W - 80.49' - 10" Oak  
N25°W - 69.66' - 10" Basswood  
N38°E - 46.35' - chiseled "x" in west end of concrete  
ring on drive culvert.