

**SURVEY &
REMONUMENTATION**

DEC 07 1994

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 24 9 46 AM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Carol Woolley

LIBER 4, PAGE 8

Register of Deeds Stamp & File Number

For corners in COMMISSION
Clinton
(County)

Located In: Corner Code ##

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>7N</u> R <u>4W</u> | <u>I-11</u> |
| | T _____ R _____ | <u>J-11</u> |
| | T _____ R _____ | <u>K-11</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Arden S. Pierson P. S. a field survey on October 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

From Clinton County Surveyor notes - Chas E. Hollister- Deputy Surveyor - March, 1894.

- I-11 - Used corner for division
- J-11 - Iron bolt with stones around it
- K-11 - Stone set with brick around it

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 35, Dallas Township

- I-11 (NW corner) - Found 1" pipe bent to point of large pointed stone-Moved stone & Set Standard Clinton County Monument.(buried 8")
- J-11 (N 1/4 corner) - Found large bolt with stones around it-Removed bolt & Set Standard Clinton County Monument.(buried 8")
- K-11 (NE corner) - Found brick and stone remains at recorded distance from North 1/4 Corner-Set Standard Clinton County Monument.(buried 8")

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>I-11 (NW corner)</u> (Standard Clinton County Monument)	<u>J-11 (N 1/4 corner)</u> (Standard Clinton County Monument)	<u>K-11 (NE corner)</u> (Standard Clinton County Monument in Monument box)
Steel anchor post -S41°E- 32.36'	N & T E. side 3" hickory -N11°W- 22.45'	N & T S. side tel. pole -N73°E- 34.86'
Steel anchor post -S57°W- 35.94'	N & T E. side 4" hickory -N41°W- 47.91'	N & T N. side power pole -N80°E- 32.84'
N & T SW side tel. pole stub-N38°E- 31.25'	N & T SW side 4" hickory -N57°W- 41.88'	S. post arrow sign post -S87°E- 27.65'
Power pole -N76°E- 60.77'	N & T S. side 17" maple -N73°W- 82.85'	Stop sign post -S70°W- 28.86'

*Standard Clinton County Monument is a 2" steel tube, 30" long with a 3 1/2" breakaway magnetic base and stamped brass cap.

Signed by Arden S. Pierson

Date NOVEMBER 24, 1993

Surveyor's Michigan License No. 13039

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 12/8/93
J. J. J.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983

