

SURVEY & REMONUMENTATION

FEB 02 1998

**REMONUMENTATION
SECTION 13, DUPLAIN TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 004 PAGE 212

For corners in Clinton (County) Located In: Corner Code #

1. Public Land Survey	T	8N	R	1W	M-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
Oct 17 9 18 AM '97
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Wendy A. Papineau, in a field survey on June 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 Standard East 1/4 Corner Section 13, T8N-R1W
Wood post placed by Robert Clark Jr., D.S. Jan. 26, 1831
S 8 W 32 lks (21.12') 20" Sugar
N 6 1/2 W 21 lks (13.86') 15" Beach

Unrecorded survey by James Porter (E.D.I.) Oct. 1987, Job 644-F (rev). Ran the East line of Sections 13, 24, 25 and 36 in searching for reliable positions for government corners along this line

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Standard East 1/4 Corner Section 13, T8N-R1W
James Porter when running the East line of said Sections above, single proportioned (from M-13 thru M-5) corner positions. We found no evidence of anything being set.
Calculated a position on the Michigan Meridian at a midpoint between Standard Section Corners of Section 13. This position falls 2' S. of an old fence line to the West.
There appears to be no conflicting evidence and this position is accepted as a careful and faithful determination of the position of the original corner.
Approved by the joint Clinton/Shiawassee County Remonumentation Peer Review Group August 13, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard East 1/4 Corner Section 13, T8N-R1W
Placed a Clinton County Monument, 2"x30" steel pipe, 3 1/4" brass cap and plastic base with a magnet, in a monument box.
West 6.30' Centerline Meridian Road
West 30.87' Set PK w/tag #39096 S. fc P/P
N85E 30.30' Set pk w/tag #39096 N. fc P/P
N60W 43.56' Set NET #39096 S. fc 8" Ash
S30E 31.30' Top center of N. end 12" corr. plastic culv.

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 8/13/97
J. J. J.



Signed by Wendy A. Papineau Date Oct. 8, 1997

Surveyor's Michigan License No. 41919