

**SURVEY & REMONUMENTATION**

FEB 02 1998

**REMONUMENTATION**

**SECTION 25, DUPLAIN TOWNSHIP**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**LIBER 004 PAGE 216**

**RECORDED**

**Oct 17 9 18 AM '97**

REGISTER OF DEEDS  
 CLINTON COUNTY, MICH.

*Carole Winkley*

**Register of Deeds Stamp & File Number**

For corners in Clinton (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 1W	M-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Wendy A. Papineau, in a field survey on June 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-10 Standard East 1/4 Corner Section 25, T8N-R1W

Wood post placed by Robert Clark Jr., D.S. Jan. 26, 1831  
 N 53 W 3 lks (1.98') 8" Beech  
 S 33 W 41 lks (27.06') 12" Lynn

Clinton County Survey Records (Source & date unknown)  
 "Set stone, two bricks on NE side stone"  
 S 87 W 1.99 lks (1.31') 8" Hickory

Unrecorded survey by James Porter (E.D.I.) Oct. 1987, Job 644-F (rev). Ran the East line of Sections 13, 24, 25, and 36 in searching for reliable positions for government corners along this line.

APPROVED BY  
 CLINTON COUNTY PEER GROUP  
 DATED 8/13/97

*J. J. J.*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-10 Standard East 1/4 Corner Section 25, T8N-R1W

Found no evidence of hickory. Calculated a position on the Michigan Meridian at a midpoint between Standard Section Corners of Section 25. Excavated a 2.0' dia. hole 3.5' deep, found no evidence of the record stone and bricks. Also, there is no evidence of occupation.

There appears to be no conflicting evidence and this position is accepted as a careful and faithful determination of the position of the original corner.

Approved by the joint Clinton/Shiawassee County Remonumentation Peer Review Group August 13, 1997.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-10 Standard East 1/4 Corner Section 25, T8N-R1W

Placed a Clinton County Monument, 2"x30" steel pipe, 3 1/4" brass cap, stamped M-10 T8N-R1W PS 41919, and plastic base with magnet in a monument box.

N45E 25.09' Set 1/2" rod w/flagging  
 N50W 23.79' Set 1/2" rod w/flagging  
 S45E 23.26' Set 1/2" rod w/flagging  
 S50W 18.10' Set 1/2" rod w/flagging



Signed by Wendy A. Papineau

Date Oct. 9, 1997

Surveyor's Michigan License No. 41919