

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Clinton County (County)	Located In:	Corner Code //
1. Public Land Survey	T 8N R 1W	1-4
	T 8N R 1W	1-5
	T 8N R 1W	#7
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary C. Bilow, in a field survey on April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-4: Corner established by U.S. Government Deputy Surveyor R. Thomas in 1831 - accessories: W. Oak 18, N88W, 25 links & W. Oak 13, S72E, 31 links, F. A. Gould, RLS #309, in 1945, records in Field Book 16, page 107; "Sugar 24, N3E, 39.2'; W. Oak 30, S48-1/2E, 41.4'; W. Oak 26, S44W, 58.8'." J. F. Quine, RLS #10704, recorded corner under Act 74, PA 1970 in Liber 1, Page 817.

1-5: Corner established by U.S. Government Deputy Surveyor R. Thomas in 1831 - accessories: Pine 12, S45E, 23 links & Sugar 14, N59W, 30 links, J. F. Quine, RLS #10704, recorded corner under Act 74, PA 1970 in Liber 1, Page 821.

#7: Found no record of this corner ever being established.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-4: Found 1/2" x 1-1/2" triangular shaped iron 0.8' under dirt at the intersection of Upton and Ridge roads and recovered two (2) of Quine's accessories. Accepted corner as the best evidence of the original GLO corner.

1-5: Found railroad spike, as set by Quine, flush with pavement and recovered two (2) of his accessories. Accepted corner as best evidence of GLO corner.

#7: Established corner midway on line between corners K-3 and K-4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-4: Found 1/2 x 1-1/2" triangular iron
S15E 77.84', Nail & Michigan Department
of Natural Resources Tag in 42" Oak
S40W 68.66', N&T in Power Pole
S50W 60.15', N&T in 39" Oak
S70W 4.37', 1/2" T-Bar

1-5: Found railroad spike
N67W 73.44', N&T in Power Pole
NOE 33.99', N&T in 9" Aspen
S25W 43.46', N&T in 10" Aspen
South 7.5' & West 126' to Center-
line / East end of Bridge

#7: Set railroad spike
S85E 30.00', N&T in Power Pole
S35W 58.17', Southeast Corner of
Building
S89W 38.06', Northeast Corner of
Building
N82W 36.60', N&T in Power Pole

Signed by Gary C. Bilow Date 1/9/98
 Surveyor's Michigan License No. 26453

