

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Clinton County (County)	Located In:	Corner Code
1. Public Land Survey	T 8N R 1W	J-5
	T 8N R 1W	K-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Gary C. Bilow, in a field survey on April, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5										●	●		
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-5: Corner established by U.S. Government Deputy Surveyor R. Thomas in 1831; accessories - Beech 10, N27E, 26 links & Beech 8, S62-1/2W, 20 links. County Surveyor Hollister records in 1879 "Stone with brick and other small stones at corner." F.A. Gould, RLS #309, recorded in Field Book 16, Page 81 in 1945 "Found stone at corner." J. Quine, RLS #13704, in 1962 found stone as described by Hollister and most of Gould's witnesses. Corner recorded under Act 74, PA 1970 by J. Quine in Liber 1, Page 819.

K-5: Corner established by U.S. Government Deputy Surveyor R. Thomas in 1831; accessories - Beech 8, S4E, 9-1/2 links & Beech 5, N50W, 4 links. Corner reset in late 1950's by J. Quine, RLS #13704, as "set masonry nail." Corner recorded under Act 74, PA 1970 by G. Stevenson, RLS #13600, in Liber 1, Page 929 and by A. Pierson, RLS #13039, in Liber 2, Page 101. Both corner forms list same accessories but different monuments - Stevenson lists a masonry nail and Pierson lists a brass plug.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5: Found and accepted 1/2" iron pipe (not railroad spike as recorded) matching all four (4) of Quine's accessories.

K-5: Found brass plug and first two (2) of Stevenson's and Pierson's accessories. Accepted this corner as the best evidence of the original GLO corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5: Found 1/2" iron pipe
 N45E 33.00', Fire Hydrant
 South 62.80', Power pole
 S30W 105.30', NW corner of cement block building
 S10W 87.00', NE corner of cement block building

K-5: Found brass plug
 NE 58.13', SW corner of cement block building
 SE 59.09', NW corner of cement block building
 S50W 52.83', Center of East bolt metal utility pole
 SW 3.11', iron rod

Signed by Gary C. Bilow Date _____
 Surveyor's Michigan License No. 26453

