

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------------------------|-----------------|
| Clinton County (County) | Located In: | Corner Code #/7 |
| 1. Public Land Survey | T 8N R 1W T 8N R 1W T R T R | J-3 J-4 |
| 2. Property Controlling in Section | S T R S T R | |
| 3. Miscellaneous Property in Sec. | S T R S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on April, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | | |
| 3 | | | | | | | | | | ● | | | |
| 4 | 7 | 8 | 9 | 10 | | | | | | ● | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

J-3: Corner established by U.S. Government Deputy Surveyor R. Thomas in 1831; accessories - Sassafras 3, N72-1/2W, 14 links & Hickory 4, S7E, 6 links. County Surveyor Hollister in 1891 recorded in Volume 2, Pages 56 to 59 of the County Survey Records as "Found post - set stone." F. Gould, RLS #309, gave personal testimony to J. Quine, RLS #10704, that he recovered the stone in 1949. J. Quine recovered stone from Hollister witness in 1977 and placed a 4" x 3/4" x 18" iron plow point and monument box over high point of stone - accessories: North 29.12', Maple stump of Hollister's 1891 bearing tree; S60W 112.2', Power pole; S10W 138.3', Power pole; N80E 5.31', 1/2" iron rod set by others.

J-4: Corner not established by GLO survey. F. Gould, RLS #309, used corner in 1949. Described to J. Quine, RLS #10704, who recovered in 1977 and recorded in Field Book 20, Page 59 as "Found rusty 1" iron pipe 3" above ground" - corner not recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

J-3: Found and accepted 4" x 3/4" x 18" iron plow point in monument box as recorded. All previous witnesses to corner lost.

J-4: Found and accepted 1" iron pipe with ring of stones and recovered 1 witness from J. Quine's notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3: Found iron plow point in monument box
 N10E 30.25', Nail & Michigan Department
 of Natural Resources tag in Power Pole
 N65E 50.87', chiseled "V" in center top
 west end of culvert headwall
 N72E 72.93', chiseled "V" in center top
 east end of culvert headwall
 S48E 71.94', N&T in Crab Apple Tree clump

J-4: Found 1" rusty iron pipe with stones
 N45E 4.17' N&T in Thorn Apple Tree
 N82E 26.61', N&T in Power pole
 N25W 20.48', N&T in Thorn Apple clump
 S10E 0.45', T-Bar fence post



Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 1/9/92

02