

SURVEY &  
REMONUMENTATION

5/9/94

DEC 07 1994

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Clinton  
(County)

Located In:

Corner Code #

- |                                    |                         |                 |
|------------------------------------|-------------------------|-----------------|
| 1. Public Land Survey              | T <u>8N</u> R <u>2W</u> | <u>I-7, J-7</u> |
|                                    | T _____ R _____         |                 |
|                                    | T _____ R _____         |                 |
|                                    | T _____ R _____         |                 |
| 2. Property Controlling in Section | S _____ T _____ R _____ |                 |
|                                    | S _____ T _____ R _____ |                 |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ |                 |
|                                    | S _____ T _____ R _____ |                 |

JAN 24 9 46 AM '94

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Lance Woolley*

LIBER 4, PAGE 10

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Arden S. Pierson P.S. a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-7 - R.H. Colburn, County Surveyor, from a survey of Section 14, T8N., R2W., that "proved up corner and set stone, being intersection 14, 15, 22, & 23" in March of 1883.
- J-7 - R.H. Colburn, County Surveyor, records from a survey of Section 14, T8N., R2W., that "set quarter post in compliance with the statutes, designated by iron, spike & stone" in March of 1883.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Greenbush Township**

- I-7 - Excavated in the intersection of Williams Road and Mead Road, in line with fence line East. Found stone and witnessed for future recovery. Excavated road was patched with asphalt by Road Commission. Set Standard Clinton County Monument and monument box at corner location.
- J-7 - Excavated width of road in general area of fence line West and East. Did not find evidence of corner monumentation. Excavated area was patched with asphalt by Road Commission, set corner location by proportionate measurement East & West. Placed Standard Clinton County Monument and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| <u>I-7 (NW corner Sec. 23)</u><br>(Standard Clinton County Monument in monument box) | <u>J-7 (N 1/2 corner Sec. 23)</u><br>(Standard Clinton County Monument in monument box) |
| Nail & Tag #34976 NE side power pole -N37°W- 52.25'                                  | Face steel corner fence post -N51°E- 118.48   |
| Nail & Tag #13039 S. side wood anchor post -East- 23.58'                             | Nail & Tag N. side wood anchor post -N87°W- 26.47'                                      |
| Face Stop sign post -S73°W- 39.68'   | Nail & Tag S. side power pole -N86°E- 50.28'  |
| Nail & Tag #13039 E. side power pole -N07°W- 137.60'                                 | Nail & Tag NW side 10" Maple -S30°W- 61.96'   |

\*\*Standard Clinton County Monument is a 2" steel tube, 30" long with a 3 1/2" breakaway magnetic base and stamped brass cap.

Signed by Arden S. Pierson Date December 10, 1993

Surveyor's Michigan License No. 13039

APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 12/18/93  
8/7/9

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1983

