

**SUBVEY A
REMONUMENTATION**

DEC 07 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 24 9 46 AM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Carole Woolley

LIBER 4, PAGE 10

Register of Deeds Stamp & File Number

For corners in

Clinton

(County)

Located In:

Corner Code #:

1. Public Land Survey	T <u>8N</u> R <u>2W</u>	<u>I-7, J-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Arden S. Pierson P. S. a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-7 - R.H. Colburn, County Surveyor, from a survey of Section 14, T8N., R2W., that "proved up corner and set stone, being intersection 14, 15, 22, & 23" in March of 1883.
- J-7 - R.H. Colburn, County Surveyor, records from a survey of Section 14, T8N., R2W., that "set quarter post in compliance with the statutes, designated by iron, spike & stone" in March of 1883.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Greenbush Township

- I-7- Excavated in the intersection of Williams Road and Mead Road, in line with fence line East. Found stone and witnessed for future recovery. Excavated road was patched with asphalt by Road Commission. Set Standard Clinton County Monument and monument box at corner location.
- J-7 - Excavated width of road in general area of fence line West and East. Did not find evidence of corner monumentation. Excavated area was patched with asphalt by Road Commission, set corner location by proportionate measurement East & West. Placed Standard Clinton County Monument and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 (NW corner Sec. 23)
(Standard Clinton County Monument in monument box)

Nail & Tag #34976 NE side power pole -N37°W- 52.25'
Nail & Tag #13039 S. side wood anchor post -East- 23.58'
Face Stop sign post -S73°W- 39.68'
Nail & Tag #13039 E. side power pole -N07°W- 137.60'

J-7 (N 1/4 corner Sec. 23)
(Standard Clinton County Monument in monument box)

Face steel corner fence post -N51°E- 118.48
Nail & Tag N. side wood anchor post -N87°W- 26.47'
Nail & Tag S. side power pole -N86°E- 50.28'
Nail & Tag NW side 10" Maple -S30°W- 61.96'

**Standard Clinton County Monument is a 2" steel tube, 30" long with a 3 1/2" breakaway magnetic base and stamped brass cap.

Signed by Arden S. Pierson Date December 10, 1993

Surveyor's Michigan License No. 13039

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 12/8/93
JSP

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971.
REVISED MAY 14, 1975.
REVISED JAN., 1983

