

**SURVEY &  
REMONUMENTATION**

MAR 21 1997

COMMISSION

**REMONUMENTATION  
SECTIONS 32 & 33, ESSEX TOWNSHIP**

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 19 10 34 AM '96

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Arden S. Pierson*

LIBER 4, PAGE 180

Register of Deeds Stamp & File Number

For corners in  
Clinton  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>3W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	<u>Reg. #2</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		13		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, Arden S. Pierson P.S., in a field survey on July 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ◆ Original survey by Robert Clark Jr., DS, 1831. Corner of Sections 32 and 33, witnessed by: Lynn 16" - N88°W - 62 links; Elm 30" - N27°E - 9 links.
- ◆ Survey by H. H. Jenison, County Surveyor, dated February 22-23, 1877. Survey of Section 5, T7N, R3W -- set stone witnessed by: Maple 4" - S17-½°E - 1.73-½ links.
- ◆ Survey by H. H. Jenison, County Surveyor, dated June 4-6, 1877. Survey of Section 4, T7N, R3W, witnesses: W. Oak 34" - S22-½°E - .64 links; W. Oak 24" - N63°E - .35-½ links.

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone, crockery and four railroad spikes, and accepted as a careful and faithful reestablishment of the position of the original corner.

Removed stone and placed Standard Clinton County Monument and placed stone and railroad spikes along side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Southeast Corner, Section 32 and Southwest Corner, Section 33
- \*Set Standard Clinton County Monument
- Nail & tag #13039 in N. side Power Pole - S85°E - 377.30'
- Nail & tag #13039 in N. side Utility Pole - S81°E - 294.72'
- Face of (E-37) Pipeline Marker Post - N70°E - 71.60'
- Nail & tag #13039 in NE side Wood Anchor Post - N37°W - 44.88'

\*Standard Clinton County Monument is a 2½" dia. Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.

Signed by *Arden S. Pierson*  
Surveyor's Michigan License No. 13039

Date August 24, 1996



APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 7/17/96  
S.P.