

**SURVEY & REMONUMENTATION**

**MAR 21 1997**

**COMMISSION**

**REMONUMENTATION  
SECTION 6, LEBANON TOWNSHIP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**RECORDED**

For corners in

<u>Clinton</u>	Located in:	Corner Code #
(County)		
1. Public Land Survey	T 8N R 4W	<u>A-1</u>
Ionia County	T 8N R 5W	<u>M-1 Ionia</u>
Gratiot County	T 9N R 4W	<u>A-13 GRATIOT</u>
Montcalm County	T 9N R 5W	<u>M-13 Montcalm</u>
2. Property Controlling in Section	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____

Oct 11 8 53 AM '96  
 REGISTER OF DEEDS  
 CLINTON COUNTY, MICH.  
*Arden Pierson*  
 LIBER 4, PAGE 175  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Arden S. Pierson P.S., in a field survey on August 16, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- ◆ Original survey by Robert Clark Jr., DS, dated March 7, 1831. Intersected West Boundary at end of 5.75.86. Witnesses: Sugar 14" - S11°W - 14 links; Beech 10" - N21°E - 38 links.
  - ◆ Survey by D.W. Attenburg, DS, dated December 14-17, 1869. Post corner 2 x 2 - stones - and stones on corner. No witnesses given.
  - ◆ Survey by Charles Eddy, County Surveyor, April 10, 1902. Commencing at the NW corner of said section found stone for corner witnessed by: Apple 1-1/2" - S11-1/4°E - 69 links.

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK Nail as filed in LCRC, Liber 2, Page 16, Gratiot County Records by Thomas Mueller, PS. Dug through 6" of asphalt and found stake and pointed stone set in cairn of stones. Accepted pointed stone in cairn of stones as a careful and faithful reestablishment of the position of the original corner.

Placed 1/2" rod to point of stone and set Clinton County Monument and monument box\*.

(This is the NW Corner of Clinton County.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**NW Corner, Section 6**  
 Set Standard Clinton County Monument and monument box.  
 Nail & tag #13039 in NE side Power Pole - S73°E - 139.91'  
 Nail & tag #13039 in SW side Telephone Pole - N40°W - 47.70'  
 Nail & tag #13039 in NW side Power Pole - S69°W - 67.00'  
 Nail & tag #13039 in NW side Power Pole - S47°W - 40.70'



\*Standard Clinton County Monument is a 2 1/2" dia. Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.

Signed by Arden S. Pierson Date August 24, 1996  
 Surveyor's Michigan License No. 13039

APPROVED BY  
 CLINTON COUNTY FEELER GROUP  
 DATED 8/21/96  
 BY J 78

◆ LCRC by Thomas Mueller, PS, #25861, dated February 17, 1981, Liber 2, page 16, T9N, R4W, Northshade Township, Gratiot County. Found shaft of P.K. nail in blacktop at centerline of intersection, witnessed by:

SW - 40.58' - power pole

NW - 47.90' - telephone pole

NE - 37.80' - road sign post