

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

REMONUMENTATION SECTION 6, DALLAS TOWNSHIP LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Clinton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>4W</u>	<u>A-1</u>
	T <u>8N</u> R <u>4W</u>	<u>A-13</u>
Ionia County	T <u>7N</u> R <u>5W</u>	<u>M-13 Ionia</u>
Ionia County	T <u>8N</u> R <u>5W</u>	<u>M-13 Ionia</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECORDED
Oct 11 8 53 AM '96
REGISTERED DEEDS
CLINTON COUNTY, MICH.
Carole Stanley
LIBER 4, PAGE 174
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Arden S. Pierson P.S., in a field survey on August 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- ◆ Original Survey by Robert Clark Jr., DS, dated February 8, 1831, T8N, R4W, Section 31, Int. West Boundary at end of 6 Miles, 6.38 set post, witnessed by: W. Oak 22" - N2°E - 1.27; W. Oak 15" - N82°W - 1.14.
 - ◆ Survey by Robert Clarke Jr., DS, dated February 10, 1831, T7N, R5W, Section 1, Int. North Boundary at end of 5 Miles, 72.84. No witnesses given.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 6" piece of 1/2" pipe — dug down and found fireclay cylinder in cairn of stones. Accepted fireclay cylinder in cairn of stones as a careful and faithful reestablishment of the position of the original corner.
- Placed 1/2" rod next to fireclay cylinder in cairn of stones and set standard Clinton County Monument.*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the
- Northwest Corner, Section 6**
*Set Standard Clinton County Monument
Nail & tag #13039 in SE side 4" Oak - N80°E - 127.83'
Nail & tag #13039 in W. side Power Pole - S0°E - 141.52'
NW corner Telephone Pedestal - S15°W - 28.98'
Stop Sign Post - N20°W - 47.81'



*Standard Clinton County Monument is a 2 1/2" dia. Steel tube 30" long with a stamped brass cap and a breakaway magnetic base.

Signed by Arden S. Pierson Date August 24, 1996
Surveyor's Michigan License No. 13039

APPROVED BY
CLINTON COUNTY PIERS GROUP
DATED 8/21/96
JF