

**SURVEY & REMONUMENTATION**

DEC 07 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

JAN 24 9 47 AM '94

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
*Carol Woolley*

LIBER 4, PAGE 12

Register of Deeds Stamp & File Number

For corners in

Clinton  
(County)

Located In:

Corner Code #

- |                                       |   |    |   |    |                 |
|---------------------------------------|---|----|---|----|-----------------|
| 1. Public Land Survey                 | T | 8N | R | 4W | <u>I-1, J-1</u> |
|                                       | T |    | R |    |                 |
|                                       | T |    | R |    |                 |
|                                       | T |    | R |    |                 |
| 2. Property Controlling in Section    | S |    | T | R  |                 |
|                                       | S |    | T | R  |                 |
| 3. Miscellaneous Property in Sec.     | S |    | T | R  |                 |
|                                       | S |    | T | R  |                 |
| 4. Lot No. _____, Recorded Plat _____ |   |    |   |    |                 |
| 5. Private Claims _____               |   |    |   |    |                 |

Arden S. Pierson P.S. in a field survey on November 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

T 8N, R 4W- G.L.O. notes - Exterior of Township Surveyed by Robert Clark DS (1831) Subdivision of Township Surveyed by Orange Risdon DS 1832.

I-1 - Intersected Twp. line 73.28 chains, at 28 links (18.48') East of Standard Corner.

J-1 - Not set in G.L.O. Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Section 2, Lebanon Township**

I-1 (NW corner) - Found drag tooth in monument box - I-13 T9N, R4W- West- 20.02'

J-1 (N 1/4 corner) - Found 1/2" iron (Tingley) cap for S 1/4 corner Section 35, T9N, R4W - Dug up entire road area of both corners and found no other physical evidence - Set 1/2" rod & cap at proportioned closing distance, 11.88' East of Standard 1/4 Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 (NW corner)  
Drag tooth in monument box

J-1 (N 1/4 corner)  
1/2" rod & cap

Intersection Tallman & Gratiot Roads  
3/4" pipe in monument box -West- 20.02'  
N & T SE side power pole -N57°E- 43.16'  
N & T W. side power pole -S09°E- 134.10'  
Face road sign post -N19°E- 51.48'

Face 2" steel anchor post -N12°W- 32.86'  
SW corner telephone riser box -N19°W- 33.82'  
N & T E. side 12" Elm -N02°W- 82.61'  
1/2" iron & cap -West- 11.88'

Signed by *Arden S. Pierson*

Date NOVEMBER 17, 1993

Surveyor's Michigan License No. 13039

APPROVED BY  
**CLINTON COUNTY PEER GROUP**  
DATED 12/3/93  
*J. J. J.*

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 30, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1983

