

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

JAN 24 9 47 AM '94

REGISTER OF DEEDS
 CLINTON COUNTY, MICH.

Carol Woolley

LIBER 4, PAGE 13

Register of Deeds Stamp & File Number

For corners in

<u>Clinton</u> (County)		Located In:	Corner Code 77
1. Public Land Survey	T <u>8N</u> R <u>4W</u>		<u>K-1</u> <u>L-1</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

I, Arden S. Pierson P.S., in a field survey on November 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11			12	
5													
6	18		17		16		15		14			13	
7													
8	19		20		21		22		23			24	
9													
10	30		29		28		27		26			25	
11													
12	31		32		33		34		35			36	

A. Description of original monument and accessories and/or subsequent restoration:

T8N, R4W G.L.O. notes - Exterior of Township Surveyed by Robert Clark DS. (1831)
 Subdivision of Township Surveyed by Orange Risdon DS. (1832)

K-1 - Intersected Township line at 73.16 chains, 18 links (5.28') East of Standard Corner.

L-1 - Not set in original survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 1, Lebanon Township

K-1 (NW corner) - Gratiot County Surveyor notes indicate an iron Corner for K-13 of T9N, R4W, - Found an iron that appears to be 2 (3/4") pipes welded together with 4 stones around iron. - Set 1/2" iron & cap on Township line at 5.28' East of Standard Corner.

L-1 (N 1/2 corner) - Found 3"x 3" oak stake in center of 4 stones for L-13, T9N, R4W, - Set iron & cap in center of stake - Set iron & cap for L-1, T8N, R4W, at proportioned Closing distance from Standard Corner (2.64' East of Standard Corner)
 *(Excavated 8'x 8' area around corners)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 (NW corner)
 1/2" iron & cap

L-1 (N 1/2 corner)
 1/2" iron & cap

Iron pipes -West- 5.28'
 N & T N. side guy pole -S87°W- 179.05'
 N & T S. side power pole -N78°W- 178.34'
 Face stop sign post -N22°W- 31.55'
 Face stop sign post -S15°E- 36.72'

1/2" iron & cap -West- 2.64'
 N & T NW side power pole -N86°E- 166.17'
 N & T E. side power pole -N02°E- 56.24'
 N & T NE side power pole -N57°W- 137.45'

Signed by *Arden S. Pierson* Date NOVEMBER 17, 1993

Surveyor's Michigan License No. 13039

APPROVED BY
 CLINTON COUNTY PEER GROUP
 DATED 12/8/93

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

