

(A 01-T8N-R3W=)

M-01-T8N-R4W-LEBANON TWP (RECORD # 64)

FEB 22 1996  
RECORDED  
COMMISSION

JAN 24 9 46 AM '94

REGISTER OF DEEDS  
CLINTON COUNTY, MICH.  
Carol Woolley

LIBER 4, PAGE 11

Register of Deeds Stamp & File Number

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Clinton  
(County)

Located In: Corner Code ##

		8N	3W	A-1, B-1
1. Public Land Survey	T	---	R	---
	T	---	R	---
	T	8N	R	4W
	T	---	R	---
2. Property Controlling in Section	S	---	T	---
	S	---	T	---
3. Miscellaneous Property in Sec.	S	---	T	---
	S	---	T	---

M-01

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Arden S. Pierson P.S. October 18 93  
I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

T8N, R3W - Surveyed in April & May, 1831 by Joel Wright DS.

B-1 - Original corner obliterated

A-1 - Original corner obliterated no County Surveyor notes in Clinton County records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 6, Essex Township

B-1 (N 1/4 corner) - Found 1/2" rod 16" long - James Porter tags on witnesses - Dug 6'x 6' hole -4' deep- No other physical evidence accepted rod as corner.

A-1 (NW corner) - Found pointed stone @ North edge gravel surface plow point at NW side - Set 1/2" rod & cap - Accepted stone as corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 (N 1/4 corner)  
1/2" rod & cap

A-1 (NW corner)  
1/2" rod & cap at point of stone with plow point at NW side

- At intersection Harris & Gratiot Roads
- N & T in NW side power pole -N34°E- 71.92'
- N & T in NW side power pole -S71°W- 69.89'
- N & T NW corner RR tie anchor post -S51°W- 37.06'
- N & T NW side utility pole gate post -S65°W- 50.05'
- N & T in SW side wood gate post -S37°E- 43.26'
- N & T E. side 30" W. cherry stump -S02°E- 36.91'
- N & T E. side 20" maple -N09°E- 110.52'
- N & T W. side wood fence post -S04°W- 37.17'

Signed by Arden S. Pierson

Date NOVEMBER 17, 1993

Surveyor's Michigan License No. 13039

APPROVED BY  
CLINTON COUNTY PEER GROUP  
DATED 12/4/93  
J-75

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1973  
REVISED MAY 14, 1975  
REVISED JAN., 1983

