


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Crawford
(County)

Located In:

Corner Code #

| | | | | | | |
|---|---|------------|---|-----------|---------------|-------|
| 1. Public Land Survey | T | <u>25N</u> | R | <u>1W</u> | <u>D - 13</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 257

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 6 | | 5 | | 4 | | 3 | | 2 | |
| 5 | | | | | | | | | | | | |
| 6 | 10 | | 9 | | 8 | | 7 | | 6 | | 5 | |
| 7 | | | | | | | | | | | | |
| 8 | 13 | | 12 | | 11 | | 10 | | 9 | | 8 | |
| 9 | | | | | | | | | | | | |
| 10 | 16 | | 15 | | 14 | | 13 | | 12 | | 11 | |
| 11 | | | | | | | | | | | | |
| 12 | 19 | | 18 | | 17 | | 16 | | 15 | | 14 | |
| 13 | | | | | | | | | | | | |

I, Marvin E. Myers, in a field survey on November, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO John Brink May 1839
 Mon.-Post
 WIT: 4" W.Pine N16°E 21 lks.
 10" Aspen N40°W 60 lks.

US GLO Guy Veal 1937
 Mon.-Accepted intersection of roads as best available position of original corner.
 Set 10" long x 6" dia. concrete block to mark corner.
 WIT: Set witness corner 24"x6" dia. with 3" Brass Tablet N50°E 70 lks.

L.2, pg.436
 Mon.-1 1/2" pipe with 1/2"x24"
 Bar in mon. box by intersection of Co. Road 602 & Old 144
 WIT: 12" Elm N20°W 90.67'
 9" N.Pine N45°W 79.60'
 8" Maple N70°W 67.80'

R.T. Ostling May 15, 1962
 Mon.-Pd. pipe
 WIT: 8" Maple N26°W 67.9'
 12" Elm N73°W 90.9'
 8" N.Pine N35°W 79.7'
 1/2"x24" Bar South 33.0'

G.D. Henning Aug. 24, 1973
 L.279, pg.544
 Mon.-Pipe in corner 4' N of C road US Survey 1937
 WIT: 8" Maple N26°W 67.9'
 12" Elm N73°W 90.9'
 8" Norway N55°W 79.7'
 Henning 1958

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found old water valve with axle shaft for corner at intersection of road on fence line South
 Found 1/2" Bar South 33.0 feet

Accepted as the best available evidence of the position of the Original Corner.

CRAWFORD COUNTY

PEER GROUP APPROVAL


DATE NOV 22, 1996

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced old water valve with monument box with Standard Crawford County monument
 WIT: Nail & tag in 6" W.Pine N60°E 83.31'
 Nail & tag in Stop Sign Post East edge N27°W 42.37'
 Nail & tag in Fence Post S05°W 33.82'
 Nail & tag in Sign Post West edge S20°W 23.99'



Signed by Marvin E. Myers

Date NOV 22, 1996

Surveyor's Michigan License No. 31600