

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

LIBER 4 PAGE 45

Located in: Corner Code #

1. Public Land Survey

T25N R1W G-13
T R
T R
T R

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
29th DAY OF Sept, 1999 AT
9:00 am. IN LIBER 4
PAGE 45
Lester Moore
Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey May 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is present in cell G12.

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1839
SET POST
PITCH PINE 6" N59°E 36 LKS
PITCH PINE 6" N47°W 35 LKS

T.N. CANADA 1937
LOCATION DETERMINED BY STUMP OF AN ORIGINAL BEARING TREE
SET CONC MON 6" DIA X 24" BRASS CAP & STEM (REMAINS OF ORIGINAL BEARING TREES)
J. PINE STUMP 12" N47°W 35 LKS (LOCAL BEARING TREES)
J. PINE 7" N56 1/2°E 91 1/2 LKS
NORWAY PINE 3" N42 3/4°W 63 1/2 LKS (NEW BEARING TREES)
NORWAY PINE 5" N28 1/2°E 132 LKS
NORWAY PINE 4" N23 1/2°W 125 LKS

WILLIAM BURT 1852
FD POST
S PINE 10" S49°E 30 LKS
Y. PINE 6" S45°W 25 LKS

LCRC 1970'S L2, P434
N56°E 60.3' 7" J. PINE
N43°W 41.8' 3" NORWAY
N28°E 87.1' 5" NORWAY
N23°W 82.8' 4" NORWAY

LARRY L. CAVANAGH, 1973
FD GLO MONUMENT
N42 3/4°W 41.9' 3" NORWAY (37) 12"(73) 18' (99)
N28 1/2°E 87.12' 5" NORWAY(37) 18"(73) 18' (99)
N23 1/2°W 82.83' 4" NORWAY(37) 14"(73) 17"(99)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND GLO MONUMENT
13' (NOW 18") NORWAY PINE N42 3/4°W 63 1/2 LKS
5' (NOW 18") NORWAY PINE N28 1/2°E 132 LKS
4" (NOW 17") NORWAY PINE N23 1/2°W 125 1/2 LKS
10" W. PINE S25°W 47.11' LEEMON TAG IN TREE
9" B OAK S65°E 75.15' LEEMON TAG IN TREE

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT GLO MONUMENT IN PLACE
W/P. NAIL & TAG IN 18" NORWAY PINE N42 3/4°W 42.06'
NAIL & TAG IN 18" NORWAY PINE N28 1/2°E 86.70'
NAIL & TAG IN 17" NORWAY PINE N23 1/2°W 82.99'
NAIL & TAG IN 10" WHITE PINE S25°W 47.11'
NAIL & TAG IN 9" BLACK OAK S65°E 75.15'
CARSONITE POST NORTH 24.8'

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE Sept 10, 1999

Marvin E. Myers MEM

Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date Sept. 14, 1999
Surveyor's Michigan License NO. 17614