

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

17 AUG 99 12:32 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

For corners in

Crawford

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>25N</u> R <u>1W</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER 4 PAGE 18

I, Marvin E. Myers, in a field survey on July 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

U.S.G.L.O - June 1937

Mon- 6"x24" Concrete monument with Std. Brass tablet

L3, P51 LCRC June 1991 N.C. Caldwell #12018

Wit: 8" B. Oak N22 1/2°E 60 lks.

Mon - Found 1/2" pipe & accessories recorded in L.1, P. 192

4" J. Pine S47°E 84 lks.

replaced 1/2"x24" iron pipe with 5"x5"x36" concrete

5" B. Oak S21 1/4°W 70 1/4 lks.

monument with brass tablet below surface in monument box and is accepted as the best available evidence of the position of the original corner.

9" J. Pine N36 3/4°W 18 lks.

L1,P192 LCRC Nov 13, 1972 J.H. Granger, #16041

Wit: Carsonite post West 33.5

Mon - Set 1/2" Iron Pipe

12" W. Oak S39°W 52.50

15" Tri-Oak N73°E 45.05'

12" W. Pine N62°W 62.05

15" Pine S51°E 51.80'

10" B. Oak N34°E 77.03

14" Poplar N79°W 31.05'

1/2" rebar with cap # 12018 West 33.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument and accessories recorded in L. 3, P. 51; found accessories recorded in L. 1, P. 192 Accepted monument as the best available evidence of the position of the Original corner. Left monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - 5"x5" concrete monument with brass tablet.

Wit: Carsonite post West 33.5

12" W. Oak S39°W 52.50

12" W. Pine N62°W 62.05

10" B. Oak N34°E 77.03

1/2" rebar with cap # 12018 West 33.00

15" Tri-Oak N73°E 45.05'

15" Pine S51°E 51.80'

14" Poplar N79°W 31.05'

CRAWFORD COUNTY

PEER GROUP APPROVAL

DATE June 7 1999

Marvin E. Myers M.E.S.

Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600



Date Aug 24, 1998