

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Crawford County

**LIBER**

**4**

**PAGE**

**48**

Located in:

Corner Code #

1. Public Land Survey

T25N	R1W	J-13
T	R	
T	R	
T	R	

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
 29th DAY OF Sept, 1999 AT  
 9:00 am/pm, IN LIBER 4  
 PAGE 48.

*Sandra Moore*

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey May 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1839  
 SET POST  
 PITCH PINE 9' N33 1/2°E 53 LKS  
 PITCH PINE 9' N66°W 44 LKS

JAMES GRANGER, RLS 1972  
 LCRC L1, P193  
 FD MON WITH 1/2' ROD  
 SAME WITNESSES AS ABOVE

T.N. CANADA 1937  
 "FD NO EVIDENCE"  
 SET CON MON 6" DIA X 24"  
 BRASS CAP & STEM AT  
 PROP DIST.  
 (LOCAL BEARING TREES)  
 B. OAK 14" N20 1/2°E 258 LKS  
 J. PINE 12" N55 3/4°W 130 LKS  
 (NEW BEARING TREES)  
 B. OAK 8" N15 3/4°E 268 LKS  
 J. PINE 7" N20°W 228 LKS

C. EUGENE OSTLING, RLS 1972  
 L265, P613  
 FD CONC MON  
 G.D. HENNING WIT  
 24" NORWAY PINE S9°W 72.6'  
 5" NORWAY PINE S67°W 128.9'  
 20" B. OAK N20°30'E 170.3'

LCRC 1970'S L2, P433  
 CONC MON  
 NORWAY PINE 24" S9°W 72.6'  
 NORWAY PINE 5" S67°W 128.9'  
 B. OAK 20" N20 1/2°E 170.3'

C. EUGENE OSTLING, RLS 1972  
 LCRC L1, P53  
 SAME WITNESSES AS ABOVE

G.D. HENNING, RLS 1978  
 L357, P416  
 NO MON MENTIONED  
 24" R. PINE S9°W 72.6'  
 5" R. PINE S67°W 128.9'  
 20" B. OAK N30°30'E 170.3'  
 12" B. OAK N16°E 176.9'

JAMES GRANGER, RLS 1972  
 RECORDED SURVEYS  
 L123, P42; L123, P29; L123, P40  
 L123, P41  
 ALL LIST S 1/4 COR (NO MON)  
 WIT: PROP. MARKER DUE SOUTH 32.9'  
 30" PINE S5°W 72.20'  
 COR FENCE POST S45°E 57.40'

GARY G. WILSON, LLS 1992  
 PLACED ORIGINAL BROKEN TOP ON  
 GLO MON BASE & RAISED W/1/2'  
 RE-ROD  
 N18°E 111.92' SWLY COR HSE FOUNDATION  
 S38°E 167.36' NW COR OF POOL HSE  
 S32°W 81.45' 8" RED PINE  
 N68°W 146.08' 12" B. OAK

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND GLO MONUMENT 1.5' BELOW SURFACE  
 FOUND 4' CONCRETE MONUMENT CALLED ECC POINT ON SURVEY IN SURVEY LIBER 383, PAGE 117 S10°E 2.2'  
 FOUND ALL 1992 WITNESSES  
 FOUND B OAK N15 3/4°E 176.9' (8" 37) (32" 99)  
 FOUND B OAK N20 1/2°E 170.3' (14" 37) (34" 99)

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD CRAWFORD COUNTY MONUMENT (TOP 12" OVER US-GLO MONUMENT TO BRING TO SURFACE)  
 WIT: NAIL & TAG IN SWLY COR HSE FOUNDATION N18°E 111.92'  
 NAIL & TAG IN NW COR POOL HSE S38°E 167.36'  
 NAIL & TAG IN 8" RED PINE S32°W 81.45'  
 NAIL & TAG IN 12" BLACK OAK N68°W 146.08'  
 FOREST SERVICE CARSONITE POST SOUTH 23.6'

CRAWFORD COUNTY  
PEER GROUP APPROVAL

DATE Sept 10, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh*  
Surveyor Michigan License NO. 17614

Date Sept. 14, 1999