

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

For corners in
Crawford County

LIBER

4

PAGE

49

Located in:

Corner Code #

1. Public Land Survey

T25N	R 1W	K-13
T	R	
T	R	
T	R	

FILED FOR RECORD THIS
 29th DAY OF Sept, 1999 AT
 9:00 @/pm, IN LIBER 4
 PAGE 49
 Sandra Moore
 Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey May 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1839
 SET POST
 YELLOW PINE 6° N76°E 20 LKS
 YELLOW PINE 5° N43°W 65 LKS

T.N. CANADA 1937
 FD 3X3 WOODEN POST 1" ABOVE GROUND
 SET CONC MON 6" DIA X 24"/BRASS CAP & STEM
 REMAINS OF ORIGINAL BEARING TREES
 N PINE 14° N48°E 44 LKS
 N PINE ST. 9° N23°W 7 LKS
 N PINE ST. 8° N44 1/2° W 65 LKS
 LOCAL BEARING TREES
 W. OAK 18° N33 /14°E 117 LKS
 W. OAK 13° S18°W 142 LKS
 NEW TREES MARKED
 POPLAR 10° N71°E 98 LKS
 POPLAR 6° N28 1/2°W 23 LKS

WILLIAM BURT 1852
 FOUND POST
 Y. PINE 10° S46°E 14 LKS
 Y. PINE 9° S35°W 12 LKS

JAMES GRANGER, RLS 1972
 L164, P301; L148, P466
 NO MONUMENT MENTIONED
 15° PINE N10°E 60.90'
 18° PINE N20°W 55.30'
 12° OAK S50°E 56.55'

GARY G. WILSON, LLS 1992
 FD GLO MON WITH BRASS CAP
 S59°E 57.52' 10" & 14" TW. B. OAK STUMPS
 N12°E 61.75' 18" R PINE
 N30°W 56.35' 20" W. PINE
 N60°E 100.49' 8" R MAPLE
 S26°W 36.18' 4" R. MAPLE
 S 15.2' CARSONITE POST

JAMES GRANGER, RLS 1972
 LCRC, L1, PAGE 193
 FD BRASS MON
 SAME WITNESSES AS ABOVE

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND GLO MONUMENT
 FOUND ALL 1992 WITNESSES
 FOUND 30' R. OAK N33°E 77.2' (CALLED 18" W. OAK IN 1937)

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT US-GLO MONUMENT IN PLACE
 WIT: NAIL & TAG IN 10" & 14" TW. B OAK STUMPS S59°E 57.52'
 NAIL & TAG IN 18" R. PINE N12°E 61.75'
 NAIL & TAG IN 20" W. PINE N30°W 56.35'
 NAIL & TAG IN 8" R MAPLE N60°E 100.49'
 NAIL & TAG IN 4" R MAPLE S26°W 36.18'
 CARSONITE POST SOUTH 15.2'

CRAWFORD COUNTY
 PEER GROUP APPROVAL
 DATE Sept 10, 1999

Marvin E. Myers
 Marvin E. Myers, P.S.
 County Surveyor



Signed by *Larry L. Cavanagh*
 Surveyor's Michigan License NO. 17614

Date Sept. 14, 1999