

MAR 22 1999

LIBER 3 PAGE 328

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

Crawford
(County)

Located In:

Corner Code #

1. Public Land Survey

T 25N R 3W

T 25N R 2W

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

M-8
A-8

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 10:00 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Marvin E. Myers, in a field survey on July 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, DS
Mon. - Post
8" Pine S65°W 25 lks.
8" Pine N73°W 21 lks.

Jan 15, 1990 Carl R. Johnson, P.S. 30083
Mon - Set DNR Monument

L.3 P.25 Indian Glens of the AuSable #5
Aug 1971 C.E. Ostling, #12026
Mon - Not given

LCRC May 30, 1998 Carl R. Johnson, P.S. 30083 (not recorded)
Mon - Set DNR Mon. midway and on line between Section corners.
Wit: 14" R. Oak N14°W 13.7
5" R. Oak N62°E 24.1
4" R. Oak S33°E 19.4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Monument of record. Found (dead) 4" R. Oak S33°E 19.4; found 14" R. Oak (wind blown down); found 5" R. Oak (wind blown down) Accepted DNR monument as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - DNR monument left in place.
Wit: Set nail & tag W. side 12" Oak South 24.19
Set nail & tag S. side 14" Oak S79°W 52.52
Set nail & tag NE. side 3" Maple N49°W 47.94
Set nail & tag W. side 6" Oak N06°E 33.14
Set Carsonite Post West 1.0

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Aug 24, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Aug 24, 1998