

MAR 22 1999

LIBER 3 PAGE 330

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 25N R 3W

T 25N R 2W

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

M-10  
A-10 ✓

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

29 SEP 98 10:00 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on July 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 G.L.O - 1839 John Brink, DS  
Mon. - Post  
12" Pine S42°W 65 lks.  
10" Pine N85°W 85 lks.

L4, P1-14 Indian Glens of the AuSable #6  
Oct 1973 B. Feldhauser 10685  
Mon - not shown

CRAWFORD COUNTY  
PEER GROUP APPROVAL

DATE Aug 21, 1998

*Marvin E. Myers*

Marvin E. Myers, P.S.  
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no evidence of monument or accessories. Reestablished corner by single proportion measurement between M-9 & M-11. North 2644.39 to M-9 and South 2644.39 to M-11. Accepted position as a careful and faithful establishment of the Position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Set Standard Crawford County Monument.  
Wit: Set nail & tag in S side 6" J. Pine N49°E 79.67  
Set nail & tag in NW side 6" J. Pine N19°E 60.14  
Set nail & tag in E side 4" J. Pine N29°W 82.58  
Set nail & tag in S side 4" J. Pine N61°W 108.94  
Set Carsonite Post West 1.0



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date Aug 24, 1998