

MAR 22 1999

LIBER 3 PAGE 331

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N R 3W
 T 25N R 2W
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

M-11
A-11 ✓

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 10:01 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on July 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, DS May 31, 1953 G. D. Henning, #2240
Mon. - Post Mon - unknown
12" Pine S38°W 07 lks.
12" Pine N24°W 16 lks.

L.160, P.555 G.D. Henning #2240, June 1972 L4, P1-14 Indian Glens of the AuSable #6
Mon - 1/2" Bar Oct 1973 B. Feldhauser 10685
Wit: 4" J. Pine S46°E 20.5 Mon - not given
 10" J. Pine N42°E 23.1
 4" J. Pine N44°W 27.1
 4" J. Pine S45°W 28.4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron in centerline of Pioneer Road. Found concrete plat monument North 33.16 on right of way of Pioneer Road. Accepted 1/2" as the best available evidence of the Position of the Original corner. Replaced 1/2" bar with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument.
Wit: Set nail & tag NW side 14" J. Pine N53°E 77.94
 Set nail & tag in E side 7" J. Pine S25°W 46.85
 Found Concrete Plat Monument North 33.16
 Nail & tag in E side S17°E 32.74
 Set Carsonite Post South 30.0

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Aug 21, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31800

Date Aug 24, 1998