

MAR 29 2000

## LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  Crawford	Located in:	Corner Code #	STATE OF MICHIGAN CRAMFORD COUNTY RECORDED
(County)			17 AUG 99 12:29 P.X.
1. Public Land Survey	T R		17 MUU 77 12=27 Fafia
1.1 upio Lana Guivey	T <u>25N R 2W</u> TR	C-13	SANDRA MOORE REGISTER OF DEEDS
Property Controlling in Section	STR STR	***************************************	
3. Miscellaneous	STR		
Property in Sec.	STR		Register of Deeds Stamp & File Number
4. Lot No, Rec 5. Private Claims	orded Plat		1 A B C D E F G H I J K L M
	TIDED 4 E	PAGE 03	2 -6 -5 -4 -3 -2 -1 -1
	LIBER 4 F	PAGE 03	3
I, Marvin E, Myers, In a field survey on March, 1999 do hereby state that under requirements of P.A. 4 -7 - 8 - 9 - 10 - 11 -			
regulations and rules therefore as required in the current manual of survey instructions of the United States			tes 6 18 17 16 15 14 13
Department of the Interior, Bure	the 7		
corner points mentioned in lines	ard 8 19 20 21 22 23 24		
of Land Surveyors or by a Decr	ed, g		
found as expressed below:			10 30 29 25 27 26 25
NOTE: Not more than 2 corners, all in the same town and range, may be recorded			12 - 31 - 32 - 33 - 34 - 35 - 36
on this certificat	e.		
A. Description of origina	al monument and accessories and	i/or subsequent restorati	
G.L.O - 1838	George D. Henning R.	L.S.	
John Brink D.S.	Unrecorded survey De		
Mon Post	Mon: 1/2 buggy axle se	et in 1937 from the stumps of th	ne original U.S. BT's, Position verified from
10" Pitch Pine N78°W		*	
10" Pitch Pine N51 1/	2°E 26 links Wit: 16" Norway Pine i 6" Jack Pine N65		ine S42°W 21.1'
^ P 111 F	1.0		

George D. Henning R.L.S.

Unrecorded survey February, 1942

Mon: 1/2 budgy axle

Wit: 16" Norway Pine N82°E 1.16 1/2

6" Jack Pine N65°W 47 1/2

10" Jack Pine S42°W 32

14" White Pine S72 1/2°E 1.58

Mon - unknown

Wit: none given

Plat of MOON RIVER HEIGHTS

March 1964 by C,E, Ostling #12026

Plat of Johnston Acres by G. D. Henning

Roscommon County Records, 1954

Mon: 1" x 1" x 36" iron in corner

Wit: 16" Yellow Pine N82°E 76.9'

6" Jack Pine N66°W 30.7"

10" Jack Pine S42°W 21.1'

14" White Pine S72 1/2°E 104.6"

Plat of Jonassen Subdivision by G.D. Henning, P.S. #2240

Mon - unknown

Wit: unknown

## B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 1" x 36" iron (buggy axle)

Found 16" Yellow Pine N82°E 76.9'

Found 10" Jack Pine S42°W 21.1'

Found 6" Jack Pine N66°W 30.7'

Found 14" White Pine \$72 1/2°E 104.6'

Accepted 1" iron buggy axle as a perpetuation of the Original Government Corner. Replaced 1" iron with Standard Roscommon County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Roscommon County Corner

Set nail & tag in 12" White Pine S72°E 48.86'

Set nail & tag in 16" Black Oak \$53°W 31.92'


Set nail & tag in Power Pole S08°E 51.78'

Set Carsonite Post N42°W 25.98'

Signed by

PEER GROUP APPROVAL

Marvin E. Myers, P.S. **County Surveyor** 



Date June 9, 1999