

APR 27 1995

COMMISSION

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE DEC 29 1994

LIBER 3 PAGE 171

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N, R 2W E-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
30th DAY OF Dec, 1994 AT
4:20 am (pm) IN LIBER 3
PAGE 171.

E. J. ...
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Dec 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO-D. Petibone 1852
 Mon-Set Post
 Wit- 9" Spr. Pine N67°W 42 lks.
 10" Spr. Pine N28°E 74 lks.
 G. Henning 6-9-78
 Mon-found 1/2" bar
 Wit-12" J. Pine S40°W 61.3
 Utility Pole S23°45'E 64.2

- R. Ostling 9-1956
 Mon- Pipe
 Wit- None given

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" x22" iron bar inside pipe alongside rotten wood post & glass 48" deep at intersection of Pioneer and Deerheart Valley roads. Replaced in exact location with standard Crawford County monument. Verified position by measurement to G. Henning Witnesses. Accepted as the best available evidence of the position of the Original Corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Mon-Set standard Crawford County Monument marked cap "31600, T25N, R2W, E-11".
 Wit-Found utility pole, set nail & tag NE side S23°E 65.08
 Found Blaze scribed NBT in face 19" J. Pine S44°W 61.30
 Set nail & tag NW side 12" R. Pine S55°W 70.15
 Set nail & tag NW side utility pole N54°E 43.29
 Set nail & tag E. side 13" TW. B. Oak N36°W 67.04



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Dec 29, 1994