

APR 27 1995

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE 12-29-1994

LIBER 3 PAGE 169

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 2W	G - 9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
30<sup>th</sup> DAY OF Dec., 1994 AT  
4:20 am (pm) IN LIBER 3  
PAGE 169.

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on December 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO-D. Pettibone 1852  
Mon-Set post  
WIT: 14" Poplar S29°W 29 lks.  
8" Birch S53°E 34 lks.

R. Ostling July 1957  
Mon-Iron Pipe  
WIT: 10" Maple N28½°E 59.2'  
5" Balsam S80½°W 48.8'

N. Parker July 10, 1978 L.2, pg. 177 LCRC  
Mon-Iron Pipe  
WIT: 10" Maple N28½°E 59.2'  
5" Balsam S80½°W 48.8'

R. Ostling Sept. 1956  
Mon-Iron Pipe  
WIT: BT 10" Maple N28½°E 59.2'  
BT 5" Balsam S80½°W 48.8'

R. Ostling Aug. 1957  
Mon-Iron Pipe  
WIT: 10" Maple N28½°E 59.2'  
5" Balsam S80½°W 48.8'  
½" bar West on R/W line

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument-Found ½" x 18" bar over ¾" I.D. x 26" iron pipe alongside 3½" x 3½" x 20" Cedar Post 0.70' West of centerline Chase Bridge Road  
WIT: Fd. ½" bar N85°W 32.83'  
Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Std. Crawford County Mon. stamped "T25N R2W G-9 31600" in exact location of cedar post in mon. box  
WIT: Fd. ½" bar N85°W 32.83'  
Set wit. tag & nail N. side U. Pole S89°E 27.94'  
Set wit. tag & nail SW side 24" W. Pine S29°E 118.88'  
Set wit. tag & nail NE side 9" W. Pine N32°W 50.03'  
Set wit. tag & nail SE side 21" W. Pine S72°W 80.64'  
Set carsonite post S83°E 29.71'



Signed by Marvin E. Myers

Date Dec 27, 1994

Surveyor's Michigan License No. 31600