

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	✓ T26N R 4W	M - 13
	✓ T25NR 4W	M - 1
	✓ T26N R3W	A - 13
	✓ <u>T 25N R3W</u>	<u>A - 1</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
19 DEC '97 2:38 P.M.
SANDRA HODRE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat LIBER
5. Private Claims _____

3 PAGE 290

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14	1						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	2						
11												
12	31	32	33	34	35	3						
13												

I, Marvin E. Myers, in a field survey on September, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. Robert T. Ostling R.L.S., December 1960
April 16 1839 Unrecorded survey
H. Brevoort D.S. & James H. Mullet D.S. Mon: no description provided
Wit: no witnesses provided;
Post corner of Towns 25&26 Tie to N 1/4 corner with a distance of 2624.4' provided.
18" yellow pine S20W 35 Links
10" Yellow Pine S34E 25 Links

Norman F. Parker R.L.S. # 16939 Liber 1 Page 175, 28 March 1972
Mon: P.K. nail in pavement over 1 1/4" pipe
Wit: Face Power Pole N38°W 43.5'
Face Power Pole S53°W 56.8'

Marvin E. Myers P.S.#31600 Liber 312 Page 305, 2 February, 1994
Mon: Pk. Nail of record

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE OCT 16, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Rail Road spike 0.15' below pavement surface. 2.5 North of the intersection of the centerline of West Four Mile Road and South Oak Road. Power poles of previous record have been removed. Measured distance to North 1/4 corner (2624.88(m)) and compared to Ostling's record distance (2624.40'(R)) Accepted position as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County monument in pavement monument box.
Wit: Set nail & tag in E. side 18" Oak Az. 29° 64.92
Set nail & tag in W side 6" Maple Az. 164° 72.39
Set nail & tag NW side Utility Pole Az. 243° 64.61
Set nail & tag SW side 12" Oak (clump) Az. 320° 83.36



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date 00 27 97