

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

LIBER

3 PAGE 268

Located in: Corner Code #

1. Public Land Survey

T 25N	R 4W	M-3
T 25N	R 3W	A-3
T	R	
T	R	

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR THE

20 DAY OF Nov, 1997 AT

9:30 am/pm, IN LIBER 3 of 1

PAGE 268

Sandra Moore

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON P. BREWER
SET POST IN 1852
Y. PINE 8 N72°W 9 LINKS
W PINE 10 S7°W 30 LINKS

NORMAN F. PARKER 16939
LIBER 138, PAGE 313
FD 1/2" BAR IN ROAD INTERSECTION
NO. WITNESSES

NORMAN F. PARKER 16939
LCRC LIBER 2, PAGE 51 1973
1/2" BAR IN 1 1/4" PIPE BY R. OSTLING 1960
BLAZE 16" N. PINE S39°W 54.61'
BLAZE 7" OAK S25°E 29.08'
FENCE COR N41°W 41.82'

Sh

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2" X 1.3" PIPE WITH 1/2" BAR INSIDE
FENCE CORNER N41°W 41.82'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CRAWFORD COUNTY MONUMENT STAMPED 17614, 1997
NAIL & TAG IN 12" NORWAY N44°E 45.45'
NAIL & TAG IN P. POLE N43°W 38.48'
NAIL & TAG IN 19" NORWAY S46°W 77.20'
NAIL & TAG IN 14" W. OAK S77°E 161.71'
CARSONITE POST S45°W 52.89'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Oct 16, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date Oct, 22, 1997