

**SURVEY & REMONUMENTATION**

APR 07 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Crawford County

**LIBER**

**3 PAGE 270**

Located in: Corner Code #

1. Public Land Survey

T26N	R3W	C-13
T25N	R3W	C-1 ✓
T	R	
T	R	

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
20 DAY OF Nov, 1997 AT  
9:30 am/pm, IN LIBER 3 of 4  
PAGE 270.

*Sandra Moore*

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON P. BREWER 1852  
SET POST CORNER  
WIT ASPEN 6" N33°W 13  
PINE 24" N50°E 45

KENNETH J. OSTLING 1975  
LEFT 1 1/4" PIPE IN PLACE  
FROM PREVIOUS SURVEYS  
NO WITNESSES

KENNETH J. OSTLING 1954  
FD MSHD PAV'T BOX  
NO WITNESSES

NORMAN F. PARKER 1973, LCRC L2, P51  
MONUMENT BOX IN BLACKTOP  
65.80' WEST OF CENTERLINE OF SOUTH  
BOUND I-75

KENNETH J. OSTLING, 1974  
1 1/4 IRON BAR IN PLACE  
FROM PREVIOUS SURVEY  
NO WITNESSES

MARVIN E. MYERS 31600, 1991, LCRC L3, P38  
MON. 1 1/2 SOLID IRON BAR IN MON. BOX  
WIT: PK NAIL IN TOP OF GUARD POST NORTH 15.23'  
PK NAIL N45°W 31.39'  
PK NAIL S50°W  
PK NAIL SOUTH 15.65'  
WEST END OF BRIDGE DECK EAST 9.90'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2 STEEL ROD IN MONUMENT BOX  
PK NAIL IN GUARD RAIL NORTH 15.23'  
PK NAIL IN GUARD RAIL N50°W 31.39'  
PK NAIL IN GUARD RAIL SOUTH 15.65'  
WEST END OF BRIDGE DECK EAST 9.90'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1 1/2" STEEL ROD (LEFT IN PLACE) STAMPED 17614  
NAIL & TAG IN GUARD RAIL SOUTH 15.65'  
NAIL & TAG IN GUARD RAIL N56°W 31.43'  
NAIL & TAG IN GUARD RAIL NORTH 15.27'  
CARSONITE POST NORTH 18.43'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**CRAWFORD COUNTY**  
**PEER GROUP APPROVAL**  
DATE Oct 16, 1997

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date Oct 27, 1997

