

APR 27 1995

COMMISSION

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Dec 22, 1994

LIBER 3 PAGE 150

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 3W	C - 10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
30th DAY OF Dec., 1994 AT
4:20 am (pm) IN LIBER 3
PAGE 150

Elizabeth H. Wiland
Registered Professional Surveyor & File Number

I, Marvin E. Myers, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO-A.P. Brewer 1852
Mon-Set Post
WIT: 14" Aspen N30°E 26 lks.
10" Aspen S37°W 94 lks.

B. Jones Apr. 24, 1991
L.3, pg.83 LCRC
Mon-2" metal post
WIT: 6" Poplar N50°E 24.10'
cedar post S65°E 22.0'
4" Poplar S10°E 22.15'
4" Poplar N60°E 12.00'

M.E. Myers 1993
Mon-Fd. 1/2" iron bar
WIT: nail S. side 4" Poplar N62°E 11.7'
nail E. side 6" Poplar N04°W 66.9'
nail SW side cedar post S09°E 22.1'
nail W. side 8" Poplar S05°E 22.8'
NE cor. metal fence post South 0.40'

G. Henning 1944
Mon-Fd. at rd. intersection
old fence on line East
WIT: None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - found 1/2" x 18" iron bar
WIT: Fd. nail N. side 15" B.Oak S75°E 48.62'
Fd. nail SW side 3" cedar post S68°E 22.13'
Fd. nail W. side 6" Poplar S06°E 22.77'
Fd. nail NW side 7" Poplar stump N55°E 23.72'
Fd. nail W side 15" J.Pine N16°E 49.39'
Fd. nail E. side 6" Poplar N02°W 66.88'
S. face 3" cedar DNR wit. post North 0.39'

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Std. Crawford County Mon. stamped "T25N R3W C-10 31600 in exact location of 1/2" bar
WIT: Fd. nail N. side 15" B.Oak S75°E 48.62'
Fd. nail SW side 3" cedar post S68°E 22.13'
Fd. nail W. side 6" Poplar S06°E 22.77'
Fd. nail SE side 6" Poplar N68°E 11.70'
Fd. nail NW side 7" Poplar stump N55°E 23.72'
Fd. nail W. side 15" J.Pine N16°E 49.39'
Fd. nail E. side 6" Poplar N02°W 66.88'
S. face 3" cedar post North 0.39'
Set carsonite post North 3.88'
NE edge metal fence post South 0.45'



Signed by Marvin E. Myers

Date Dec 29, 1994

Surveyor's Michigan License No. 31600