

APR 27 1995

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 22, 1994

**LIBER 3 PAGE 146**

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 STATE OF MICHIGAN

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 3W	C - 11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

COUNTY OF CRAWFORD  
FILED FOR RECORD THIS  
30<sup>th</sup> DAY OF Dec, 1994 AT  
4:20 am/pm IN LIBER 3  
PAGE 146

*Elizabeth D. Wiland*  
Register of Deeds  
Stamp & File Number

I, Marvin E. Myers, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO-A.P. Brewer 1852 Mon-Set Post WIT: 8" Tamarack N44°W 53 lks. 6" Spruce S22°E 108 lks. old section cor. N45°E 212 lks.	L. Cavanagh Sept. 30, 1985 L.2, pg.266 LCRC Mon-Fd. 4" wood post (in swamp) WIT: 4" Spruce S80°W 7.8' 3" Spruce N24°W 4.5' 5" Spruce N50°E 18.25' 4" Spruce S44°E 12.45'	B. Jones Apr. 24, 1994 L.3, pg.83 LCRC Mon-Set 1/2" iron WIT: 4" Spruce N32°W 4.00' 6" Spruce S41°E 13.55' 6" Spruce S10°W 19.00' 6" Spruce S78°W 7.77'
L. Cavanagh Sept. 30, 1985 L.242, pg.11 Mon-Fd. 4" wood post (in swamp) WIT: 4" Spruce S80°W 7.8' 3" Spruce N24°W 4.5' 5" Spruce N50°E 18.25' 4" Spruce S44°E 12.45'	B. Jones Apr. 24, 1991 L.331, pg.329 Mon-Set 1/2" iron WIT: 4" Spruce N32°W 4.00' 6" Spruce S41°E 13.55' 6" Spruce S10°W 19.00' 6" Spruce S78°W 7.77'	M.E. Myers Mon-Fd. 1/2" Bar #23514 WIT: 3" N.Pine N20°W 4.0' 6" N.Pine S75°W 4.7' 5" N.Pine S03°W 19.0' 5" N.Pine S40°E 13.5'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Monument - Found 4" cedar post  
WIT: Fd. 5" Spruce stump S86°W 7.80'  
Fd. nail NE side 4" Spruce stump N20°W 4.78'  
Fd. nail SW side 5" Spruce N40°E 12.82'  
Fd. nail E. side 5" Spruce S05°E 18.21'  
Fd. 3" cedar post N07°E 1.06'  
Fd. 1/2" bar & cap N10°W 0.85'  
Accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon-Set std. Crawford County Mon. stamped "T25N R3W C-11 31600" over cedar post  
WIT: Fd. nail NW side 4" Spruce N56°E 18.57'  
Fd. nail SW side 5" Spruce S40°E 12.82'  
Fd. nail E. side 5" Spruce S05°W 18.21'  
Set wit. tag & nail NE side 6" Spruce N29°W 27.87'  
Set carsonite post N77°W 2.87'  
Fd. 3" cedar post N07°E 1.06'  
Fd. 1/2" bar & cap N10°W 0.85'

Signed by Marvin E. Myers Date December 29, 1994  
Surveyor's Michigan License No. 31600