

MAR 22 1989

LIBER 3 PAGE 319

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

Located in: Corner Code #

1. Public Land Survey

T25N	R 3W	D-7
T	R	
T	R	
T	R	

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
29 SEP 98 9:59 A.M.
SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey August, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

A.P. BREWER 1852, GLO SET POST Y. PINE 20° N51°W 7.77 LKS Y. PINE 18° S62 1/2E 39.8 LKS	NORMAN PARKER, RLS, 1979, L184, P263 NO MON MENTIONED WIT: 8" R.P. N17°E 45.4' 14" B.O. S19°E 44.2' FACE P.P. 35°W 60.3'
G.D. HENNING, ILS 1976, L156, P3 FD 5/8" BAR 13" OAK S45°E 75.26' 15" J. PINE N50°E 82.97' 15" J. PINE N30°W, 71.24'	N. PARKER, R.S., 1982 LCRC L2, P249 FD 1" BAR M.P.O.L. BTW C-7 & E-7 NO WIT.
NORMAN PARKER, RLS, 1979, L184, P53 NO MON MENTIONED OR WIT.	M. MYERS, L.S., 1992, L350, P186 REF. L2, P249

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 14" BOAT SPIKE
FOUND NE & SW WITNESS FROM 1979

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD CRAWFORD COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 14" N. PINE N30°E 49.80'
(OLD WIT) FACE OF 8" (NOW 14") N. PINE N17°W 45.1'
NAIL & TAG IN SIDE OF P. POLE S35°W 60.59'
NAIL & TAG IN 14" B. OAK S10°E 53.17'
CARSONITE POST N35°W 36.96'

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE Aug 27, 1998

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date 8/24/98
Surveyor's Michigan License NO. 17614