

APR 27 1995

COMMISSION

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 22, 1994

LIBER 3 PAGE 148

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 3W	D - 11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
30<sup>th</sup> DAY OF Dec, 1994 AT  
4:20 am (pm) IN LIBER 3  
PAGE 148.

Register of Deeds Stamp & File Number  
Register of Deeds

I, Marvin E. Myers, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-A.P. Brewer 1852  
Mon-Set Post  
WIT: 10" dead S.Pine N32°E 56 lks.  
12" dead S.Pine S64°W 24 lks.
- R. Ostling June 11, 1954  
Mon-Fd. stone & square bottle  
1' below surface  
WIT: Fd. remains of original B.T.'s  
Mkd. NBT 8" J.Pine S84°E 70.95'  
Mkd. NBT 14" N.Pine S11½°E 73.9'
- G. Henning Sept. 1, 1981 L.200, pg.608  
Mon-Fd. stone & square bottle  
1' below surface  
WIT: Fd. remains of original B.T.'s  
8" J.Pine S84°E 70.95'  
14" N.Pine S11½°E 73.9'
- L. Cavanagh Sept. 30, 1985  
L.242, pg.11  
Mon-Fd. 3/8" Bar  
WIT: 8" J.Pine S84°E 71.0'  
14" R.Pine S11°E 73.9'  
7" J.Pine N20°E 44.75'  
7" S.Pine N65°W 89.65'
- B.Jones Apr. 24, 1991 L.331, pg.329  
Mon-Fd. 3/8" Iron  
WIT: 8" J.Pine N78°E 49.12'  
8" J.Pine S84°E 71.00'  
14" R.Pine S11°E 73.90'  
10" S.Pine N65°W 89.65'
- B.Jones Apr. 24, 1991 L.3, pg.83 LCRC  
Mon-Fd. 3/8" Bar  
WIT: 8" J.Pine N78°E 49.12'  
8" J.Pine S84°E 71.00'  
14" R.Pine S11°E 73.90'  
10" S.Pine N65°W 89.65'
- M.E. Myers 1993  
Mon-3/8" Pipe  
WIT: Blaze N. face 24" R.Pine S05°E 73.63'  
Blaze W. face 10" J.Pine N79°E 49.28'  
Blaze SW face 10" J.Pine N21°E 19.60'  
Blaze SE face 6" J.Pine N59°W 89.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found 3/8" x 24" Iron Bar alongside 1" ID x 48" Iron pipe alongside stone over square tonic bottle  
WIT: Fd. blaze S. face 9" J.Pine N22½°E 19.40'  
Fd. nail W. side 11" J.Pine with blaze N80°E 49.15'  
Fd. blaze N. face Tw. R.Pine S05°E 74.00'  
Fd. blaze SE face J.Pine N58½°W 89.68'  
Fd. blaze S. face 9" J.Pine N22½°E 44.80'  
NE cor. 4"x4" wood post N50°W 0.57'  
Accepted as a perpetuation of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Std. Crawford County Mon. stamped "T25N R3W D-11 31600"  
WIT: Fd. blaze S. face 9" J.Pine 19.40'  
Fd. nail W. side 11" J.Pine with blaze N80°E 49.15'  
Fd. blaze N. face Tw. R.Pine S05°E 74.00'  
Fd. blaze SE face J.Pine N58½°W 89.68'  
Fd. blaze S. face 9" J.Pine N22½°E 44.80'  
NE cor. 4"x4" wood post N50°W 0.57'  
Set wit. tag & nail W. side 9" J.Pine N22½°E 19.63'  
Set wit. tag & nail W. side 16" Tw. R.Pine S05°E 74.83'  
Set wit. tag & nail NE side 7" J.Pine N75°W 39.30'  
Set carsonite post S84°E 3.94'



Signed by *Marvin E. Myers*

DATE Dec 29, 1994

Surveyor's Michigan License No. 31600