

SEP 18 1998

LIBER 3 PAGE 320

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 9:58 A.M.

SANDRA MOORE
REGISTER OF DEEDS

For corners in
Crawford County

Located in: Corner Code #

1. Public Land Survey

T25N	R 3W	E-7
T	R	
T	R	
T	R	

I, Larry L. Cavanagh, in a field survey August, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

- A.P. BREWER 1852, GLO SET POST
W. OAK 14" N34°W 25 LKS
B. OAK 14" S45°E 48 LKS
- N. PARKER, RLS 1973
LCRC L2, P75
MON 1/2" BAR
B.T. 10" OAK N23°W 37.0
B.T. 20" OAK S30°W 64.0
- NORMAN PARKER, RLS. 1979, L184, P53
MON - WIT SAME AS ABOVE
- N. PARKER, R.S, 1982
LCRC L2, P249
MON-1/2" BAR
B.T. 18" W. OAK S33°W 64.17
B.T. 12" W. OAK N11°W 36.95
B.T. 12" R. PINE S27°E 65.70
- NORMAN PARKER, RLS. 1979, L184, P53
MON 1 1/4" PIPE
WIT SAME AS ABOVE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 1/2" X 26" STEEL ROD OVER REMAINS OF WOODEN POST
FOUND 1982 SW AND SE WITNESSES
- THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD CRAWFORD COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 16" R. PINE S27°E 65.92'
NAIL & TAG IN 18" WHITE OAK S33°W 64.77'
NAIL & TAG IN 10" TWIN OAK N15°W 44.54'
NAIL & TAG IN 16" WHITE PINE N47°W 43.92'
CARSONITE POST N42°W 37.3'

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE Aug 21, 1998

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

Signed by Larry L. Cavanagh
Surveyor's Michigan License NO. 17614

Date

8/24/98

