

CRAWFORD COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF CRAWFORD

For corners in

Crawford	Located In:	Corner Code ##
(County)		
1. Public Land Survey	T <u>25N</u> , R <u>3W</u>	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED FOR RECORD THIS  
5<sup>th</sup> DAY OF Jan, 1994  
11:15 am/pm, IN LIBER 3 4c  
 PAGE 120  
*Eliel W. Wieland*  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**LIBER 3 PAGE 120**

I, Marvin E. Myers, in a field survey on \_\_\_\_\_ Dec \_\_\_\_\_, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO- Aug 1852 A.P. Brewer  
 Mon- Post  
 Wit- 7" S. Pine N75°W 98 Lks  
 8" S. Pine N48°E 140 Lks

MSHD- 1966 M.S. Koivisto  
 Mon- Fd. 1½" pipe  
 Wit- P. Pole N45°W 60.38  
 Cor. Fence Post N55E 47.30  
 Cor. Fence Post S35°E 47.33

May 1944 G. Henning  
 Mon- 1½" pipe  
 Wit- In Road intersection

Date not given- Robert Ostling  
 Mon- 1½" pipe

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1½" pipe 12 inches below surface of old Road bed verified position by measurement to corners of record and accepted as the best available evidence of the position of the Original Corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon- Set in exact location 2"x21" Standard Crawford County Monument.  
 Wit- 1" pipe 4'± above ground level S05°E 76.92  
 Top center of General telephone pedestal S45°E 45.6  
 Nail and Standard brass tag in West side Guard Post N15°W 117.04  
 Set Carsonite "Survey Marker Post West 4.06



Signed by Marvin E. Myers Date Dec 21, 1993

Surveyor's Michigan License No. 31600  
 DATE Dec 6, 1993

PEER GROUP APPROVAL