

APR 27 1995

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Dec 29, 1994

LIBER 3 PAGE 145 COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>3W</u>	<u>E - 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
30th DAY OF Dec, 1994 AT
4:20 am/pm IN LIBER 34c
PAGE 145
Right to S.W. land
Register of Deeds Stamp & File Number
Register of Deeds

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on December 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-A.P. Brewer Mon-Set Post WIT: 9" Spruce N10°W 24 lks. 10" Spruce S31°E 36 lks.	F.Arleth Aug. 8, 1978 L.172, pg.15 Mon-None WIT: 12" Tam. N76°E 44.1' 8" Tam. N45°W 52.5'	M.E.Myers Mon-R.R. spike G. Rd. WIT: nail SE side 10" Spruce N38°E 55.9' nail S. side 8" Fir N67°E 59.9' nail S. side 4" Spruce N77°W 50.0' nail SW side 12" Spruce S10°E 98.6'
G.Henning May 1944 Mon-Fd. Std. Mon. Box in cent. of Hwy. WIT: None	G.Henning Aug. 3, 1979 L.182, pg.293 Mon-Fd. 3/4" bolt WIT: 12" Tam. N76°E 44.1' 8" Tam. N45°W 52.5' 8" Tam. S16°E 98.1'	
R.Ostling date unknown Mon-MSHD pav't box WIT: None		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found R.R. spike at surface in centerline South Grayling Road 0.30' South and 0.08' West of found 12" cabin spike 0.5' undersurface 0.55' South of found mon. box 15" under surface in centerline South Grayling Road
WIT: Fd. nail W. side 15" Tamarack S12°E 99.25'
Fd. nail SE side 7" Tamarack N44°E 55.14'
Fd. nail SE side 11" Tamarack N73°E 59.44'
Fd. nail S. side 6" Tamarack N77°W 44.92'
Fd. 11" Tamarack (dead) N84°E 43.85'
Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Std. Crawford County Mon. stamped "T25N R3W E-11 31600" over set PK nail over center of found mon. box in mon. box
WIT: Fd. nail W. side 15" Tamarack S12°E 99.25'
Fd. nail SE side 7" Tamarack N44°E 55.14'
Fd. nail SE side 11" Tamarack N73°E 59.44'
Fd. nail S. side 6" Tamarack N77°W 44.92'
Set carsonite post 33.94'



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Dec 29, 1994